SUMMARY OF QUANTITIES				100% STATE	I000	
	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITES	CONSTRUCTION TYPE CODE URBAN	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	21,986	21,986	
	40600300	AGGREGATE (PRIME COAT)	TON	11	11	
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	15	15	
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	893	893	
	40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	370	370	
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	10,780	10,780	
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	990	990	
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	90	90	
	44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	109,930	109,930	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	990	990	
	44000600	SIDEWALK REMOVAL	SQ FT	90	90	
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,195	1,195	
	44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	2,200	2,200	
	44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	55	55	
	44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	220	220	
	44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	825	825	
	44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	1,100	1,100	
	55039700	STORM SEWERS TO BE CLEANED	FOOT	486	486	
	60251730	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 23 FRAME AND GRATE	EACH	2	2	
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	4	4	
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5	
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	12	12	
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	152	152	
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
	67100100	MOBILIZATION	L SUM	1	1	
	70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	

SUMMARY OF QUANTITIES				100% STATE	I000	
	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITES	CONSTRUCTION TYPE CODE URBAN	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	19,321	19,321	
	70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182	
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38,643	38,643	
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2,703	2,703	
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	61	61	
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	557	557	
•	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	182	182	
•	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38,643	38,643	
•	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,703	2,703	
•	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	61	61	
•	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	557	557	
•	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,542	1,542	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,225	1,225	
•	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	291	291	
•	88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,718	3,718	
	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	514	514	
	X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5,780	5,780	
	XX002873	BRICK SIDEWALK REMOVAL	SQ FT	1,016	1,016	
	XX004688	BRICK PAVER SIDEWALK	SQ FT	1,016	1,016	
	Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	13	13	
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

• SPECIALTY ITEM

FILE NAME = ...\general\pln59709soq.dgn	USER NAME = akeaschell	DESIGNED - AJK	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES US 34 (OGDEN AVE) – IL 43 (HARLEM AVE) TO IL 50 (CICERO AVE)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN - AJK	REVISED -			311	7-RY-1RS-1	COOK	21	3
	PLOT SCALE = N.T.S.	CHECKED - JAS	REVISED -					CONTRACT NO. 60H27		
	PLOT DATE = 4/21/2009	DATE - 4/21/2009	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		