

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000	QUANTITY
20201006	GRADING AND SHAPING SHOULDERS	UNIT	76	76	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	43	43	
40600300	AGGREGATE (PRIME COAT)	TON	43	43	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	142	142	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	143	143	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	2100	2100	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	21400	21400	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	542	542	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	48	48	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	227	227	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	160	160	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	107	107	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	305	305	
55039700	STORM SEWERS TO BE CLEANED	FOOT	40	40	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2500	2500	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	18600	18600	

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000	QUANTITY
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	900	900	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	850	850	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	840	840	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	150	150	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	18600	18600	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	900	900	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	850	850	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	510	510	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	510	510	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1202	1202	
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	900	900	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	4	4	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* SPECIALTY ITEM

FILE NAME: P:\2007\ME07888_VerVer-Phil\Cadd\W015_IL22_Shts\03500sht-sht-IL22.dgn
 PLOT SCALE: 1:8000 / 1"=100'
 USER NAME: Millennium Engineering



200 22ND Street, Suite 216, Lombard, IL 60148
 630.765.0110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 4/21/2009	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

IL ROUTE 22 (HALF DAY RD)
 STORYBOOK LN / WESTMINISTER TO LONDON LN

SUMMARY OF QUANTITIES

F.A.P. RTE. 337	SECTION 20 RS-9	COUNTY LAKE	TOTAL SHEETS 22	SHEET NO. 3
CONTRACT NO. 60H28				

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT
 P:\2007\ME07888_VerVer-Phil\Cadd\W015_IL22_Shts\03500sht-sht-IL22.dgn