

SUMMARY OF QUANTITIES				
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	57	57
40600300	AGGREGATE (PRIME COAT)	TON	141	141
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	27	27
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	2,720	2,720
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9,494	9,494
42001300	PROTECTIVE COAT	SQ YD	200	200
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	8,198	8,198
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	87,785	87,785
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	559	559
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2,795	2,795
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1,118	1,118
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,118	1,118
55039700	STORM SEWERS TO BE CLEANED	FOOT	1,500	1,500
60250200	CATCH BASINS TO BE ADJUSTED	EACH	24	24
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	26	26
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,849	6,849
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,075	2,075
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	68,968	68,968
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5,706	5,706
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,086	2,086
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	845	845
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,283	2,283
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,075	2,075
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	68,968	68,968
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5,706	5,706
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,086	2,086

* SPECIALTY ITEM

SUMMARY OF QUANTITIES				
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN	
			100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	845	845
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,074	1,074
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	930	930
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	2,000	2,000
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	206	206
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,274	3,274
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	16,574	16,574
X4421000	PARTIAL DEPTH PATCHING	TON	691	691
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	4,110	4,110
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	50	50
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	5	5

* SPECIALTY ITEM

PLOT DATE : 4/22/2009
FILE NAME : K:\1122814\Hicks Road\Cad\Sheets\Hicks 500.dgn
PLOT SCALE : 1:50
USER NAME : J.Tresey
MODEL : Default



Excellence through Ownership

200 West Front Street
Wheaton, IL 60187

DESIGNED - MAK	REVISED - ---
DRAWN - JMT	REVISED - ---
CHECKED - BLB	REVISED - ---
DATE - 4/22/2009 8:44:08 AM	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL RTE 53 (HICKS RD)

SUMMARY OF QUANTITIES

F.A.P. RTE. 2592	SECTION 531 RS-2	COUNTY COOK	TOTAL SHEETS 26	SHEET NO. 3
CONTRACT NO.60H34				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

SCALE: 1"=50'

SHEET NO. ___ OF 26 SHEETS

STA. _____ TO STA. _____