

URBAN

CODE NO.	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100 % STATE	
				ROADWAY 1000	GUARDRAIL SFTY - 3J
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	19117	19117	
40600300	AGGREGATE (PRIME COAT)	TON	335.5	335.5	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	242	242	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,438	1,438	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,028	8,028	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	75	75	
42400800	DETECTABLE WARNINGS	SQ FT	30	30	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	95,560	95,560	
44000600	SIDEWALK REMOVAL	SQ FT	75	75	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	115	115	
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	6,583	6,583	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	100	100	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	805	805	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	840	840	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	4,838	4,838	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,725	1,725	
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,315		1,315
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE J (SPECIAL) TANGENT	EACH	19		19
63200310	GUARDRAIL REMOVAL	FOOT	722		722
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	

* SPECIALTY ITEM

URBAN

CODE NO.	SUMMARY OF QUANTITIES ITEM DESCRIPTION	UNIT	TOTAL RURAL QUANTITIES	CONSTRUCTION TYPE CODE 100 % STATE	
				ROADWAY 1000	GUARDRAIL SFTY - 3J
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	50,150	50150	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	21	21	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	100,299	100299	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	92	92	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	56	56	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	39	39	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	20.6	20.6	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	100,299	100299	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	92	92	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	56	56	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	39	39	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	960	960	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	36	36	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	960	960	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	77	77	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	268	268	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	128.5	128.5	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	5,017	5017	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2	