

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
20200100	EARTH EXCAVATION	CU YD	80	80	
35800200	AGGREGATE BASE REPAIR	TON	110	110	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45	
40600300	AGGREGATE (PRIME COAT)	TON	210	210	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	6	6	
40600535	LEVELING BINDER (HAND METHOD), N70	TON	15	15	
40600895	CONSTRUCTING TEST STRIP	EACH	4	4	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	610	610	
40600990	TEMPORARY RAMP	SQ YD	770	770	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	240	240	
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	5,300	5,300	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	30	30	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	2,000	2,000	
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	52,300	52,300	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	30	30	
44000600	SIDEWALK REMOVAL	SQ FT	2,000	2,000	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800	800	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1,380	1,380	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	660	660	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	360	360	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	170	170	
55039700	STORM SEWERS TO BE CLEANED	FOOT	2,500	2,500	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10	
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	65	65	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES				URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9,730	9,730	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,900	2,900	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	80,500	80,500	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8,600	8,600	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,100	2,100	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6,900	6,900	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	3,600	3,600	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16,500	16,500	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	950	950	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	27,300	27,300	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,850	2,850	
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	700	700	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2,600	2,600	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,200	1,200	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	990	990	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	950	950	
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,500	3,500	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52	
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2,850	2,850	
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	140	140	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

FILE NAME = m:\pro\3368\3368_20\design\proposed\plan\3368_20-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = aleu	DESIGNED - RJR	REVISED -
	DRAWN - RJR	REVISED -
PLOT SCALE = 1:8000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/28/2009	DATE - 4/22/2009	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 171 / THATCHER AVENUE
DES PLAINES RIVER ROAD TO NORTH OF FOREST PRESERVE AVENUE
SUMMARY OF QUANTITIES

F.A.P. RTE. 372	SECTION 2009-055 RS	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3
SCALE: STA. TO STA.			CONTRACT NO. 60H39	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				