

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	79	79
40600300	AGGREGATE (PRIME COAT)	TON	416	416
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	941	941
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	383	383
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8,724	8,724
42001300	PROTECTIVE COAT	SQ YD	34	34
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	103,849	103,849
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	1,950	1,950
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	1,120	1,120
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	560	560
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	270	270
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,250	1,250
55039700	STORM SEWERS TO BE CLEANED	FOOT	216	216
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000 URBAN
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	36,000	36,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,274	1,274
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	106,724	106,724
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,655	4,655
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1,200	1,200
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4,526	4,526
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	455	455
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,650	4,650
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,274	1,274
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	106,724	106,724
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4,655	4,655
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1,200	1,200
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4,526	4,526
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	455	455
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,060	1,060
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	960	960
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,945	1,945
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	250	250
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4,362	4,362
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	18	18

* SPECIALTY ITEM

FILE NAME = D160H43-shr-500.dgn
PLOT DATE = 4/22/2009



CHRISTIAN-ROGE & ASSOCIATES, INC.
ENGINEERS-PLANNERS-SURVEYORS
211 WEST WACKER DRIVE
CHICAGO, ILLINOIS 60606
PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED -	G.F.L.	REVISED -	
DRAWN -	A.C.S.	REVISED -	
CHECKED -	M.P.	REVISED -	
DATE -	APRIL 2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL RTE. 171 (WILL COUNTY LINE TO IL RTE. 83)

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. 13+41 TO STA. 279+05

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
577	3114 RS-1	COOK	26	3
			CONTRACT NO. 60H43	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				