



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 8, 2009

SUBJECT: FAP Route 336
Section 111R-RS
McHenry County
Contract No. 60H46
Item No. 173, May 15, 2009 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages i of the Table of Contents to the Special Provisions.
2. Revised page 19 of the Special Provisions.
3. Deleted pages 20 - 39 of the Special Provisions.

This Addendum deletes the Special Provision "HOT MIX ASPHALT PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS (D-1)".

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll, Chief
Bureau of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Bill Frey, Estimates

TBW:MS:jc

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
COMPLETION DATE PLUS WORKING DAYS.....	2
DELAYED START OF MULTIPLE CONTRACTS (DISTRICT ONE)	2
MAINTENANCE OF ROADWAYS	3
STATUS OF UTILITIES TO BE ADJUSTED	3
GRADING AND SHAPING SHOULDERS	3
FINE AGGREGATE FOR HOT- MIX ASPHALT (HMA) (D-1)	4
HOT MIX ASPHALT MIXTURES, EGA MODIFIED PERFORMANCE GRADED (PG) ASPHALT BINDER5	
COARSE AGGREGATE FOR HOT-MIX ASPHALT (HMA) (D-1)	5
HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE)	8
USE OF RAP (DIST 1).....	12
HOT MIX ASPHALT – DENSITY TESTING OF LONGITUDINAL JOINTS (D-1)	18
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON	
ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS	40
TRAFFIC CONTROL PLAN.....	43
TEMPORARY INFORMATION SIGNING	44
APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE	
ILLINOIS STATE BORDERS (BDE)	45
CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE).....	45
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)	46
EQUIPMENT RENTAL RATES (BDE).....	54
FLAGGER AT SIDE ROADS AND ENTRANCES (BDE)	55
HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE)	55
HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE)	57
HOT-MIX ASPHALT – TRANSPORTATION (BDE)	58
LIQUIDATED DAMAGES (BDE).....	59
MULTILANE PAVEMENT PATCHING (BDE).....	59
NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT	
CONTROL DEFICIENCY DEDUCTION (BDE)	59
PAYMENTS TO SUBCONTRACTORS (BDE)	60

Revised 05/08/2009

DENSITY CONTROL LIMITS			
Mixture Composition	Parameter	Individual Test ^{2/}	Minimum Unconfined Test
IL-9.5, IL-12.5	Ndesign ≥ 90	92.0 – 96.0 %	90.0 %
IL-9.5, IL-9.5L, IL-12.5	Ndesign < 90	92.5 – 97.4 %	90.0 %
IL-19.0, IL-25.0	Ndesign ≥ 90	93.0 – 96.0 %	90.0 %
IL-19.0, IL-19.0L, IL-25.0	Ndesign < 90	93.0 – 97.4 %	90.0 %
All Other	Ndesign = 30	93.0 ^{1/} - 97.4 %	90.0 %

1/ 92.0 % when placed as first lift on an unimproved subgrade.

2/ “Density values” shall meet the “Individual Test” density control limits specified herein.

Pages 20 - 39 have been Deleted.
 The next page is 40.

Revised 05/08/2009