

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20201006	GRADING AND SHAPING SHOULDERS	UNIT	484	484
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	98	98
40600300	AGGREGATE (PRIME COAT)	TON	488	488
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	14	14
40600535	LEVELING BINDER (HAND METHOD), N70	TON	20	20
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	800	800
40600990	TEMPORARY RAMP	SQ YD	910	910
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10,600	10,600
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	121,700	121,700
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1,850	1,850
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	550	550
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2,990	2,990
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1

* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17,780	17,780
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2,100	2,100
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	173,900	173,900
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	8,700	8,700
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2,400	2,400
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	600	600
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	22,700	22,700
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	700	700
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	116,000	116,000
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,900	2,900
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	800	800
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	940	940
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	894	894
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,150	1,150
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	6,600	6,600
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5

FILE NAME = m:\proj\3368\3368_19\design\proposed\plan\3368_19_03-Quantities.dgn



Cioba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - NT	REVISED -
	DRAWN - NT	REVISED -
PLOT SCALE = 1:2000' / IN.	CHECKED - WBL	REVISED -
PLOT DATE = 4/28/2009	DATE - 4/22/09	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 31
JOHNSBURG ROAD TO US 12 (TYRON GROVE ROAD)
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 27 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336	111 R-RS	MCHENRY	27	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H46	