

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
20200100	EARTH EXCAVATION	CU YD	300	300
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	30	30
35800200	AGGREGATE BASE REPAIR	TON	350	350
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20	20
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	166	166
40600300	AGGREGATE (PRIME COAT)	TON	828	828
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	22	22
40600535	LEVELING BINDER (HAND METHOD), N70	TON	40	40
40600895	CONSTRUCTING TEST STRIP	EACH	4	4
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,570	2,570
40600990	TEMPORARY RAMP	SQ YD	3,600	3,600
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4	4
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	20,900	20,900
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	50	50
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	500	500
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	207,000	207,000
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	80	80
44000600	SIDEWALK REMOVAL	SQ FT	500	500
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,700	1,700
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	2,660	2,660
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	1,080	1,080
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	230	230
55039700	STORM SEWERS TO BE CLEANED	FOOT	5,700	5,700
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	6	6
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	20	20
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	255	255
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	30	30

\* DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 1000
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	34,000	34,000
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	12,900	12,900
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	251,400	251,400
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	50,100	50,100
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	2,700	2,700
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	9,900	9,900
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	7,800	7,800
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	49,700	49,700
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	4,300	4,300
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	83,800	83,800
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	16,700	16,700
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	900	900
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3,300	3,300
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	2,600	2,600
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3,050	3,050
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	2,890	2,890
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	7,300	7,300
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	11,200	11,200
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	340	340
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

FILE NAME = N:\PROJ\3388\3388\_23\Design\Proposals\Plan\3388\_23-03-Quantities.dgn



**Ciorba Group, Inc.**  
CONSULTING ENGINEERS  
5507 North Cumberland Avenue, Suite 402  
Chicago, Illinois 60656  
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - EPS	REVISED -
PLOT SCALE = 1:8000 / IN.	DRAWN - EPS	REVISED -
PLOT DATE = 4/22/2009	CHECKED - WBL	REVISED -
	DATE - 4/22/09	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**CERMAK ROAD  
WEST OF WOLF ROAD TO IL 43 (HARLEM AVENUE)  
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 38 SHEETS STA. TO STA.

F.A.U. RTE. 1453	SECTION (78-2 & 551)Y-RS-1	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 3
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H47	