SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES 1000	CONSTRUCTION TYPE CODE					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	16						
40600300	AGGREGATE (PRIME COAT)	TON	75						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12						
40600895	CONSTRUCTING TEST STRIP	EACH	1						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	673						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3135						
42001300	PROTECTIVE COAT	SQ YD	245						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	37315						
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	820						
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	90						
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	70						
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	240						
55039700	STORM SEWERS TO BE CLEANED	FOOT	1400						
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30						
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	95						
60404940	FRAMES AND GRATES, TYPE 23	EACH	20						
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	20						
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3						
67100100	MOBILIZATION	L SUM	1						
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1						
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1908						
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	65						
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1845						
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4398						
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1012						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5050						
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	65						
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1845						

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES 1000	CONSTRUCTION TYPE CODE					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4398						
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1012						
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4						
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	57						
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1470						
44004600	SIDEWALK REMOVAL AND REPLACEMENT	SQ FT	250						
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	84						

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\steedpd\d0137655\d145300-sht-plan.dgn	USER NAME = steedpd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/17/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
MORGAN ST.--79TH STREET TO 63RD STREET

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

O.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0054	1922 RS-3	COOK	20	3
		CONTRACT NO. 62042		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT