

O.R.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
213	0102 RS-7	COOK	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
62046				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100% STATE				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	200	200				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14				
40600300	AGGREGATE (PRIME COAT)	TON	136	136				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	14	14				
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1910	1910				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	236	236				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2865	2865				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	31862	31862				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	885	885				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	646	646				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1402	1402				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	10,200	10,200				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	957	957				
60260100	INLETS TO BE ADJUSTED	EACH	1	1				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5565	5565				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000 100% STATE				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41534	41534				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	140	140				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	136	136				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	73	73				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	41534	41534				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	140	140				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	136	136				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	512	512				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	377	377				
88600600	DETECTOR LOOP REPLACEMENT	FOOT	35	35				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103				

\* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
119TH STREET  
IL-45 TO IL-83

Rev.

4/14/2009 8:50:40 AM C:\WORK\PROJECTS\119TH STREET\119TH STREET.dwg