IMPROVEMENT ENDS
STA. 155+00

N

CHRISTIANA AVE.
℄ STA 145+78

PROP. HMA SURFACE REMOVAL, 2¼"
PROP. POLYMERIZED LEVELING BINDER
(MACHINE METHOD), IL-4.75, N50, ¾"
PROP. HMA SURFACE COURSE, MIX "D", N70, 1½"

SPAULDING AVE.
℄ STA. 148+82

SAWYER AVE.
℄ STA. 152+18

KEDZIE AVE.
℄ STA. 155+50

PARKING

PARKING

PARKING

PARKING

NO PARKING

MATCHLINE STA. 141+00

PARKING

PARKING

PARKING

PARKING

NO PARKING

LIMIT OF RESURFACING (TYP.)

HOMAN AVE.
℄ STA. 142+17

LEGEND:

① PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 4", SKIP DASH @ 30' SKIP AND 10' DASH, WHITE (TYP.)

② PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 4", DOUBLE LINE @ 11" C-C, YELLOW (TYP.)

③ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 6", TURN LANE, WHITE (TYP.)

④ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 12", DIAGONALS @ 45°, YELLOW (TYP.)

⑤ PROPOSED THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS, WHITE (TYP.)

⑥ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 24", STOP LINE, WHITE (TYP.)

⑦ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 4", EDGE LINE, YELLOW (TYP.)

⑧ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 4", SKIP DASH @ 30' SKIP AND 10' DASH, YELLOW (TYP.)

⑨ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 6", CROSSWALK (PEDESTRIAN), WHITE (TYP.)

⑩ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 12", DIAGONALS @ 45°, WHITE (TYP.)

⑪ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 12", CROSSWALK (SCHOOL), WHITE (TYP.)

⑫ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 8", WHITE (TYP.)

⑬ PROPOSED THERMOPLASTIC PAVEMENT MARKING LINE 6", DOTTED LINE @ 2' LINE AND 6' SPACE, WHITE (TYP.)

NOTE:

LIMIT OF RESURFACING ON SIDE ROADS AND STREETS SHALL BE TO THE RADIUS OF RETURN OR AS DIRECTED BY THE ENGINEER.

ALL PERMANENT PAVEMENT MARKINGS SHALL BE THERMOPLASTIC UNLESS OTHERWISE NOTED. SEE "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" DETAIL (TC-13).

RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE USED THROUGH THE IMPROVEMEN LIMITS. SEE "DISTRICT ONE TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS" DETAIL (TC-11).

FILE NAME =	USER NAME = shiranisb	DESIGNED -	REVISED -			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pw_work\PWIDOT\SHIRANISB\d0139175\D145101-Design.dgn		DRAWN -	REVISED -	**STATE OF ILLINOIS**	**ROADWAY AND PAVEMENT MARKING PLANS**	1453	2001-144 RS	COOK	21	9
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -	**DEPARTMENT OF TRANSPORTATION**	**CERMAK ROAD /BRC RR TO KEDZIE AVE.**			CONTRACT NO. 62323		
	PLOT DATE = 4/21/2009	DATE -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	