

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2000	2000					
40600300	AGGREGATE (PRIME COAT)	TON	9	9					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	150	150					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	180	180					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	54	54					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	40	40					
40603995	^{POLYMERIZED} HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	440	440					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	230	230					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	100	100					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36.4	36.4					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	100	100					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2000	2000					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	4450	4450					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	150	150					
44000600	SIDEWALK REMOVAL	SO FT	100	100					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	180	180					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40	40					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	100	100					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	60	60					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	150	150					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	150	150					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	533	533					
50300300	PROTECTIVE COAT	SO YD	56	56					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	180	180					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	15	15					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8					X0322250	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2														
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2														
67100100	MOBILIZATION	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1														
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	900	900														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	36.4	36.4														