SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	86	86					
40600300	AGGREGATE (PRIME COAT)	TON	430	430					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	34	34					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	304	304					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	8863	8863					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	105587	105587					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	6330	6330					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	4220	4220					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2335	2335					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1					
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3700	3700					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	334	334					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	81407	81407					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	800	800					
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	55	55					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	100	100					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	387	387					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1235	1235					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	334	334					

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	81407	81407					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	800	800					
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	55	55					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	387	387					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	596	596					
*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	380	380					
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	460	460					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	437	437					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4300	4300					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\PWIDOT\MOSSSE\d0110419\sh_rdwy.dgn	USER NAME = mossse	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 '/ IN.	CHECKED -	REVISED -
	PLOT DATE = 3/26/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
846	5RS-2	WILL	31	3
		CONTRACT NO. 62648		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT