

SUMMARY OF QUANTITIES				URBAN 100% STATE					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES										CODE NO	ITEM	UNIT	TOTAL QUANTITIES									
				1000																					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	239	239																					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	21	21																					
40600300	AGGREGATE (PRIME COAT)	TON	104	104																					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	13	13																					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	70	70																					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	400	400																					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2185	2185																					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	25995	25995																					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	2360	2360																					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	795	795																					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	596	596																					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	596	596																					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	445	445																					
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3																					
63200310	GUARDRAIL REMOVAL	FOOT	113	113																					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3																					
67100100	MOBILIZATION	L SUM	1	1																					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1																					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3010	3010																					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	29784	29784																					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	11	11																					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	9950	9950																					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	29784	29784																					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	11	11																					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	230	230																					
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3																					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	154	154																					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4																					
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1025	1025																					

FILE NAME =
c:\work\p\pl\pl\am\the\00137267\002004-sh-pln.dwg

USER NAME = amtkk
PLOT SCALE = 50.0000' / 1" IN.
PLOT DATE = 4/14/2009

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 531	SECTION 2004-044RS	COUNTY WILL	TOTAL SHEETS 16	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
CONTRACT NO. 62659				

* SPECIALTY ITEMS