

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		TOTAL QUANTITIES	I000 LOC. 1	I000 LOC. 2						TOTAL QUANTITIES	I000 LOC. 1	I000 LOC. 2		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	20	16	4											
40600300	AGGREGATE (PRIME COAT)	TON	96	78	18											
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9	6	3											
40600895	CONSTRUCTING TEST STRIP	EACH	3	2	1											
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	434	291	143											
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	292	192	100											
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2163	1424	739											
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	20	20												
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	290		290											
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	25445	16946	8499											
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	5112	5112												
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	20	20												
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	595	445	150											
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SO YD	1304	858	446											
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	465	320	145											
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SO YD	125	60	65											
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SO YD	778	563	215											
50300300	PROTECTIVE COAT	SO YD	133	99	34											
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100												
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	10	10												
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	66	66												
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3												
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	3	3												
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	2	1											
67100100	MOBILIZATION	L SUM	1	0.5	0.5											
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5											
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5											
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5											
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	73	109											
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	14016	10816	3200											
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4977	4704	273											
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1198	468	730											
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	923	776	147											
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	182	73	109											
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8608	5408	3200											
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2625	2352	273											
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	964	234	730											
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	535	388	147											
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	182	111	71											
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	101	61	40											
88600600	DETECTOR LOOP REPLACEMENT	FOOT	1435	667	768											
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	309	206	103											
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1002	667	335											
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	38	34	4											
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	0.5	0.5											

\* Specialty Items