

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				100% - STATE ROADWAY	1000 RURAL
CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	2.6	2.6	
50104400	CONCRETE HEADWALL REMOVAL	EACH	3.3	3.3	
50105225	PIPE CULVERT REMOVAL (SPECIAL)	FOOT	240	240	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	368	368	
50901760	PIPE HANDRAIL	FOOT	58	58	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	76	76	
54010303	PRECAST CONCRETE BOX CULVERT 3' X 3'	FOOT	76	76	
54010405	PRECAST CONCRETE BOX CULVERT 4' X 5'	FOOT	42	42	
54215760	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 15"	EACH	8	8	
54215763	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2	
54248510	CONCRETE COLLAR	CU YD	5.7	5.7	
60237480	INLETS, TYPE A, TYPE 37 GRATE	EACH	1	1	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	3854	3854	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	21	21	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1	1	
63200310	GUARDRAIL REMOVAL	FOOT	2663	2663	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	34	34	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	9	9	
66700605	PERMANENT SURVEY TIES	EACH	12	12	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1	
67100100	MOBILIZATION	L SUM	1	1	

* SPECIALTY ITEMS