

**RESURFACING SCHEDULE**

STATION TO STATION	LENGTH (FT)	AVERAGE WIDTH (FT)	AREA (SQ. YD.)	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4" (SQ. YD.)	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" (SQ. YD.)	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70 (1 3/4") (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (1 1/2") (TON)	MATERIAL TRANSFER DEVICE (TON)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT (SQ. YD.)	TEMPORARY RAMP (SQ. YD.)
<b>US ROUTE 150</b>												
135+26 - 135+36	10	71	79			0.03		8		8	79	
135+36 - 136+25	89	71	702	702		0.28		69		69		
136+25 - 139+30	305	78	2643	2643		1.06		259		259		
139+30 - 139+62	32	78	277	277		0.11		27		27		
139+62 - 140+62	100	72	800	800		0.32		78		78		
140+62 - 143+45	283	72	2264	2264		0.91		222		222		
143+45 - 144+74	129	66	946	946		0.38		93		93		
144+74 - 148+22	348	60	2320	2320		0.93		227		227		
148+22 - 150+74.80 BK	253	60	1685	1685		0.67		165		165		
150+74.01 AH - 170+13	1939	60	12927	12927		5.17		1267		1267		
170+13 - 171+63	150	66	1100	1100		0.44		108		108		
171+63 - 173+18	155	72	1240	1240		0.50		122		122		
173+18 - 173+48	30	60	200	200		0.08		20		20		
173+48 - 175+23	175	60	1167	1167		0.47		114		114		
175+23 - 178+98.75 BK	376	56	2338	2338		0.94		229		229		
179+04.50 AH - 180+75	171	51	966	966		0.39		95		95		
180+75 - 182+80	205	62	1412	1412		0.56		138		138		
182+80 - 183+51	71	72	568	568		0.23		56		56		
183+51 - 183+82	31	66	227	227		0.09		22		22		
183+82 - 187+95	413	60	2753	2753		1.10		270		270		
187+95 - 189+35	140	66	1027	1027		0.41		101		101		
189+35 - 191+00	165	72	1320	1320		0.53		129		129		
191+00 - 193+80	280	77	2396	2396		0.96		235		235		
193+80 - 195+75	195	87	1885	1885		0.75		185		185		
195+75 - 195+85	10	87	97			0.04		9		9	97	
<b>SIDEROADS</b>												
ASHTON ST. (TO RAD. RETURN)			155		122	0.06	0.3		13		33	17
COLUMBUS (LT) (TO RAD. RETURN)			132		99	0.05	0.3		11		33	17
COLUMBUS (RT) (TO RAD. RETURN)			135		101	0.05	0.3		11		34	17
ALLEY (140+85) (TO RAD. RETURN)			30		14	0.01	0.1		3		16	17
DAYTON (TO RAD. RETURN)			128		96	0.05	0.3		11		32	17
RT TURN LN & GRAND (STOP 10' BEFORE ENTR. TO SCHOOL LOT)			1251		1215	0.50	2.5		105		36	17
RT TURN LN, ACC. LN, & HARVARD (LT) (TO RAD. RETURNS ON HARV. & BUS. ENTRANCE)			1191		1105	0.48	2.4		100		86	17
HARVARD (RT) (TO RAD. RETURN)			134		102	0.05	0.3		11		32	17
ROCK ISLAND (TO RAD. RETURN)			172		124	0.07	0.3		14		48	17
<b>TOTALS</b>				<b>43164</b>	<b>2978</b>	<b>19</b>	<b>7</b>	<b>4247</b>	<b>280</b>	<b>4247</b>	<b>526</b>	<b>153</b>