

PERMANENT PAVEMENT MARKING SCHEDULE

LOCATION STA. TO STA.	EPOXY PAVEMENT MARKING -							PREFORMED PLASTIC PVMT MARKING, TYPE B - LINE 6" (FT)	
	LINE 4"		LINE 8"	LINE 12"		LINE 24"	LETTERS & SYMBOLS (SF)		
	SOLID YELLOW (FT)	SKIP DASH YELLOW (FT)	SOLID WHITE (FT)	DIAGONAL WHITE (FT)	DIAGONAL YELLOW	STOP BAR WHITE (FT)			
135+26 TO 137+00	431.0	0.0	253.0	0.0	0.0	0.0	62.4	100.0	
137+00 TO 143+00	963.0	0.0	596.0	0.0	0.0	0.0	171.6	330.0	
143+00 TO 149+00*	2059.0	0.0	566.0	0.0	84.0	87.0	187.2	310.0	
149+00 TO 154+00	1751.0	40.0	0.0	0.0	98.0	0.0	15.6	220.0	
154+00 TO 160+00	2400.0	0.0	0.0	0.0	141.0	0.0	0.0	300.0	
160+00 TO 166+00	2400.0	0.0	0.0	0.0	141.0	0.0	0.0	300.0	
166+00 TO 172+00	2209.0	0.0	123.0	0.0	110.0	0.0	31.2	300.0	
172+00 TO 178+00**	1577.0	0.0	735.0	58.0	61.0	36.0	93.6	300.0	
178+00 TO 184+00	1972.0	0.0	119.0	0.0	30.0	0.0	31.2	300.0	
184+00 TO 190+00	2230.0	0.0	82.0	0.0	110.0	0.0	31.2	300.0	
190+00 TO 195+85	2404.0	0.0	360.0	183.0	198.0	0.0	31.2	300.0	
SUBTOTALS =		20396.0	40.0	2834.0	241.0	973.0	123.0	655.2	3060.0
TOTALS =		20,436		2,834	1,214		123	655	3,060

* Includes quantity for Grand Avenue Detail

** Includes quantity for Harvard Avenue Detail

SHORT-TERM PAVEMENT MARKING SCHEDULE

LOCATION			LENGTH (FT)	SHORT-TERM PAVEMENT MARKING		WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
STA.	TO	STA.		YELLOW (FT)	WHITE (FT)	
135+26	TO	137+00	174	0.0	69.6	23.2
137+00	TO	143+00	600	35.2	187.8	74.3
143+00	TO	149+00	600	98.0	674.0	257.3
149+00	TO	154+00	500	100.0	108.0	69.3
154+00	TO	160+00	600	120.0	120.0	80.0
160+00	TO	166+00	600	120.0	120.0	80.0
166+00	TO	172+00	600	120.0	132.7	84.2
172+00	TO	178+00	600	120.0	336.0	152.0
178+00	TO	184+00	600	120.0	130.0	83.3
184+00	TO	190+00	600	120.0	130.0	83.3
190+00	TO	195+85	585	117.0	159.5	92.2
SUBTOTALS =				1070.2	2167.6	1079.3
SUBTOTALS X 2 APPLICATIONS =				2140.4	4335.2	
TOTALS =				6,476		1,079

RAISED REFLECTIVE PAVEMENT MARKERS

STA. TO STA.	ONE-WAY WHITE	ONE-WAY AMBER	TWO-WAY AMBER	
135+26 TO 137+00	11	0	0	
137+00 TO 143+00	22	0	6	
143+00 TO 149+00	19	16	5	
149+00 TO 154+00	13	18	3	
154+00 TO 160+00	16	30	0	
160+00 TO 166+00	14	30	0	
166+00 TO 172+00	18	24	3	
172+00 TO 178+00	18	18	4	
178+00 TO 184+00	17	14	11	
184+00 TO 190+00	16	26	2	
190+00 TO 195+85	16	30	0	
SUBTOTALS		180	206	34
TOTALS		420		

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	EACH
STA 135+26 TO 195+86	420
TOTAL	420