

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE ROADWAY	100% STATE TRAFFIC SIGNAL
				1000 URBAN	Y031-1F URBAN
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1890	1890	
21400100	GRADING AND SHAPING DITCHES	FOOT	543	543	
25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36	
25100115	MULCH, METHOD 2	ACRE	0.4	0.4	
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	1178	1178	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	714	714	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	52	52	
40600300	AGGREGATE (PRIME COAT)	TON	266	266	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1767	1767	
40600990	TEMPORARY RAMP	SQ YD	865	865	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1429	1429	
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	11519	11519	
44000100	PAVEMENT REMOVAL	SQ YD	88	88	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	113241	113241	
44004250	PAVED SHOULDER REMOVAL	SQ YD	8956	8956	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	136	136	
44201294	CLASS B PATCH-EXPANSION JOINT	FOOT	124	124	
44201296	DEFORMED BARS - EXPANSION JOINT	EACH	110	110	