

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				100% STATE ROADWAY	100% STATE TRAFFIC SIGNAL
				I000 URBAN	Y031-1F URBAN
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6156	6156	
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	6196	6196	
*78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1326	1326	
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	53935	53935	
*78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	13629	13629	
*78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	4507	4507	
*78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	695	695	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	764	764	
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	2	2	
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	764	764	
*88600100	DETECTOR LOOP, TYPE I	FOOT	2366		2366
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	8	8	
X0322729	MATERIAL TRANSFER DEVICE	TON	11439	11439	
*X2503100	MOWING	UNIT	185	185	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017202	DOWEL BARS 1 1/2"	EACH	340	340	
Z0020800	EROSION CONTROL CURB	FOOT	361	361	
Z0020805	EROSION CONTROL CURB REMOVAL	FOOT	361	361	
Z0075310	TIE BARS 3/4"	EACH	314	314	

*SPECIALTY ITEM