CONTRACT NO. 70113

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(149,150)RS-3	EDGAR	83	5

SUMMARY OF QUANTITIES

LOCATION OF WORK: STA. 1681+95.00 TO STA. 2081+75.87 EDGAR COUNTY

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY 100% STATE 1000
40600990	TEMPORARY RAMP	SQ YD	175.0
40603310	HOT-MIX ASPHALT SURFACE COURSE,MIX "C", N50	TON	10,040.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	121,922.0
X4420452	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	135.0
X4420454	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	105.0
X4420456	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	60.0
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	135.0
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	105.0
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	307.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,960.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	419.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	303.0
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1.0
50200100	STRUCTURE EXCAVATION	CU YD	318.0
51500100	NAME PLATES	EACH	2.0
54001001	BOX CULVERT END SECTION, CULVERT NO.1	EACH	2.0
54001002	BOX CULVERT END SECTION, CULVERT NO.2	EACH	2.0

* SPECIALTY ITEMS

(CONT'D NEXT SHEET)

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 323 (US 36)
SECTION (149,150)RS-3
EDGAR COUNTY

SCALE: N/A DRAWN BY: CADD
DATE: 05/02/2006 CHECKED BY

PLOT DATE = 4/7/2009
FILE NAME = c:\pw_work\pwidot\sherer.ja\dms67384\tsrv.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = sherer.ja