

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(149,150)RS-3	EDGAR	83	14

SCHEDULES OF QUANTITIES

EARTHWORK SCHEDULE

	STATION	TO	STATION	20200100 EARTH EXCAVATION (CU YD)	ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	20400800 FURNISHED EXCAVATION (CU YD)	
CULVERT NO. 1								
	LT	1700+00	LT	1703+00	52.0	39.0	19.0	-20.0
	RT	1700+00	RT	1703+00	122.0	91.5	4.0	-87.5
SN 023-0010								
TBT, T1(SPL)	RT	1782+21.35	RT	1782+82.35	0.0	0.0	0.0	7.3
TBT, T1(SPL)	LT	1782+96.35	LT	1783+57.35	0.0	0.0	0.0	7.3
TBT, T1(SPL)	RT	1787+82.65	RT	1788+43.65	0.0	0.0	0.0	7.3
CULVERT NO. 2								
	LT	1817+00	LT	1820+00	20.0	15.0	149.0	134.0
	RT	1817+00	RT	1820+00	34.0	25.5	162.0	136.5
CULVERT NO. 3								
	RT	1832+83.45	RT	1835+00	50.0	37.5	25.0	-12.5
	LT	1832+83.45	LT	1835+00	56.0	42.0	18.0	-24.0
SN 023-0025								
TBT, T1(SPL)	RT	1942+59.54	RT	1843+20.54	0.0	0.0	0.0	7.3
TBT, T1(SPL)	LT	1941+48.04	LT	1942+09.04	0.0	0.0	0.0	7.3
TBT, T1(SPL)	RT	1948+46.96	RT	1949+07.96	0.0	0.0	0.0	7.3
TBT, T1(SPL)	LT	1948+71.96	LT	1949+32.96	0.0	0.0	0.0	7.3
SN 023-0030								
TBT, T1(SPL)	RT	2024+69.35	RT	2025+30.35	0.0	0.0	0.0	7.3
TBT, T1(SPL)	LT	2025+44.35	LT	2026+05.35	0.0	0.0	0.0	7.3
TBT, T1(SPL)	RT	2030+20.65	RT	2030+81.65	0.0	0.0	0.0	7.3
TOTAL =				334.0	250.5	377.0	199.5	
USE =				334.0	251.0	377.0	200.0	

*FURNISHED EXCAVATION = EARTH EXCAVATION X ADJUSTMENT FACTOR (0.75) - EMBANKMENT

SHEET 1 OF 6

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

F.A.P. ROUTE 323 (US 36)
SECTION (149,150)RS-3
EDGAR COUNTY

SCALE: N/A
DATE: 05/02/2006

DRAWN BY: CADD
CHECKED BY: