CONTRACT NO. 70113

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(149,150)RS-3	EDGAR	83	15

SCHEDULES OF QUANTITIES

LANDSCAPING SCHEDULE

	STATION	TO		STATION	AREA (ACRE)	28000250 TEMPORARY EROSION SEEDING (POUND)	25000350 SEEDING CLASS 7 (ACRE)	25000200 SEEDING CLASS 2 (ACRE)	25000400 NITROGEN FERT. (POUNDS)	25000500 PHOS FERT. (POUNDS)	25000600 POTAS. FERT. (POUNDS)	25100115 MULCH METHOD 2 (ACRE)
		CULVERT NO. 1										
LT	1700+00		LT	1703+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
RT	1700+00		RT	1703+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
		CULVERT NO. 2										
LT	1817+50		LT	1820+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
RT	1817+50		RT	1820+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
		CULVERT NO. 3										
RT	1832+83.45		RT	1835+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
LT	1832+87.12		LT	1835+00	0.2	20	0.2	0.2	18.0	18.0	18.0	0.2
				TOTAL =	1.20	120.00	1.20	1.20	108.00	108.00	108.00	1.20
				USE =	1.2	120.0	1.2	1.2	108.0	108.0	108.0	1.2

SCHEDULE NOTE: IT IS THE INTENT THAT CLASS 7 SEEDING BE PLACED ALONG WITH THE CLASS 2 SEEDING AS A SUPPLEMENTAL SEEDING TO PROMOTE ACCELERATED VEGETATION GROWTH.

EROSION CONTROL SCHEDULE

	STATION	28000300 TEMPORARY DITCH CHECKS (EACH)	28000500 INLET &PIPE PROTECTION (EACH)
	CULVERT NO. 1		
RT	1700+00.00	1.0	
LT	1700+00.00	1.0	
RT	1703+00.00	1.0	
LT	1703+00.00	1.0	
	CULVERT NO. 2		
RT	1816+54.01		1.0
LT	1816+87.64		1.0
RT	1820+00	1.0	
LT	1820+00	1.0	
	CULVERT NO. 3		
RT	1832+37.43		1.0
LT	1832+87.12	1.0	
RT	1835+00.00	1.0	
LT	1835+00.00	1.0	
	TOTAL =	9.0	3.0

28000400 PERIMETER EROSION BARRIER

	STATION	TO		STATION	(LIN FT)
	CULVERT NO. 1				
RT	1700+00.00		RT	1703+00.00	300.0
LT	1700+00.00		RT	1703+00.00	300.0
	CULVERT NO. 2				
RT	1817+11.97		RT	1820+00	228.0
LT	1817+43.42		RT	1820+00	256.6
	CULVERT NO. 3				
RT	1832+83.45		RT	1835+00	216.6
LT	1832+87.12		RT	1835+00	212.9
				TOTAL =	1514.0

*28100107 STONE RIPRAP, CLASS A4

	STATION	SQ YD	28200200 FILTER FABRIC SQ YD
	CULVERT NO. 1		
LT	1701+41.00	50.0	50.0
RT	1701+41.00	57.0	57.0
	CULVERT NO. 2		
LT	1817+93.65	54.0	54.0
RT	1817+93.65	54.0	54.0
	CULVERT NO. 3		
LT	1833+78.5	50.0	50.0
RT	1833+78.5	47.0	47.0
	TOTAL =	312.0	312.0

* THE ENGINEER MAY MODIFY LOCATIONS OF STONE RIPRAP, CLASS A4 BASED ON FIELD CONDITIONS

SHEET 2 OF 6

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

F.A.P. ROUTE 323 (US 36)
SECTION (149,150)RS-3
EDGAR COUNTY

SCALE: N/A
DATE: 05/02/2006

DRAWN BY: CADD
CHECKED BY

PLOT DATE = 4/4/2009
FILE NAME = c:\pw_work\pwidot\sherer_jm\dms87384\sex1.dgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = sherer_jm