CONTRACT NO. 70113

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	(149,150)RS-3	EDGAR	83	17

SCHEDULES OF QUANTITIES

48101200 AGGREGATE SHOULDERS, TYPE B

STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVERAGE THICKNESS (INCHES)	48101200 AGG SHLD TYPE B (TONS)
1681+95.00		1687+00.00	505.0	3	1.5	25.3
1687+00.00		1782+90.00	9590.0	3	1.5	479.5
1788+50.00		1792+41.35	391.4	3	1.5	19.6
1792+41.35		1828+50.35	3609.0	3	1.5	180.5
1828+50.35		1943+00.00	11449.7	3	1.5	572.5
1943+00.00		1944+65.00	165.0	3	1.5	8.3
1945+91.80		1947+53.00	161.2	3	1.5	8.1
1947+53.00		2025+30.00	7777.0	3	1.5	388.9
2025+30.00		2027+66.58	236.6	3	1.5	11.8
2028+59.42		2031+10.00	250.6	3	1.5	12.5
2031+10.00		2081+75.87	5065.9	3	1.5	253.3
					TOTAL =	1960.1
					USE =	1960.0

48101500 AGGREGATE SHOULDERS, TYPE B, 6"

	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
		CULVERT NO. 1				
RT	1700+41.00		1702+41.00	200.0	3	66.7
LT	1700+41.00		1702+41.00	200.0	3	66.7
		CULVERT NO. 2				
RT	1817+70.94		1819+71.07	200.1	3	66.7
LT	1817+43.42		1819+71.07	227.6	3	75.9
		CULVERT NO. 3				
RT	1832+83.45		1835+00.00	216.5	3	72.2
LT	1832+87.12		1835+00.00	212.9	3	71.0
					TOTAL =	419.1
					USE =	419.0

SCHEDULE OF DRAINAGE STRUCTURES

	STATION	20900110 POROUS GRAN BACKFILL (CU YD)	50100300 REM EXIST STRUCT NUMBER 1 (EACH)	50100500 REM EXIST STRUCT NUMBER 3 (EACH)	50200100 STRUCTURE EXCAVATION (CU YD)	51500100 NAME PLATES (EACH)	54001001 BOX CUL END SECT CULV. NO. 1 (EACH)	54001002 BOX CUL END SECT CULV. NO. 2 (EACH)	54001003 BOX CUL END SECT CULV. NO. 3 (EACH)	54010603 PCBC 6X3 (M259) (FOOT)	54020402 PCBC 4X2 (M273) (FOOT)	54021002 PCBC 10X2 (M273) (FOOT)	59300100 CONTR LOW STR. MATL. (CU YD)
CULVERT NO. 1	1701+41.00	55.0	1.0		157.0	1.0	2.0					52.0	
CULVERT NO. 2	1818+71.00	77.0			119.0	1.0		2.0		56.0			96.0
CULVERT NO. 3	1833+78.50	32.0		1.0	42.0				2.0		50.0		
	TOTALS =	164.0	1.0	1.0	318.0	2.0	2.0	2.0	2.0	56.0	50.0	52.0	96.0

SHEET 4 OF 6

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

F.A.P. ROUTE 323 (US 36)
SECTION (149,150)RS-3
EDGAR COUNTY

SCALE: N/A
DRAWN BY: CADD
DATE: 05/02/2006
CHECKED BY

PLOT DATE = 4/4/2009
FILE NAME = c:\pw_work\pwidot\sherer_jm\dms87384\sextcdgn
PLOT SCALE = 42.3529 ' / IN.
USER NAME = sherer_jm