SUMMARY OF QUANTITIES

RURAL
100% STATE
OLD US51

CODE NO.	ITEM	UNIT	TOTAL QUANTITY 1000
20800150	TRENCH BACKFILL	CU YD	12
28000500	INLET AND PIPE PROTECTION	EACH	2
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8,914
40600300	AGGREGATE (PRIME COAT)	TON	180
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	4,528
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	3,055
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	40
40600990	TEMPORARY RAMP	SQ YD	220
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX C, N50	TON	10,052
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GAL	300
40800030	AGGREGATE(PRIME COAT)	TON	6
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	558
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	12,531
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	4,083
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	174
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	85
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	220
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,320
50105220	PIPE CULVERT REMOVAL	FOOT	80
54020302	PRECAST CONCRETE BOX CULVERT 3'X2' (M273)	FOOT	40
54200445	PIPE CULVERTS, TYPE 1 RCCP 30"	FOOT	40
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11,850
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	88,599
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,306
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	88,599
X0914100	PRECAST CONCRETE BOX CULVERT END SECTIONS 3'X2'	EACH	2
XX007274	LEVELING BINDER (MACHINE METHOD) SPECIAL	TON	457

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\craigre d0112235\D570511-sht-SQQ.dgn	USER NAME = craigre	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/29/2009	DATE -	REVISED

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1476	(55,56)RS-3	McLean	24	4

CONTRACT NO. 70511

ILLINOIS FED. AID PROJECT