

SUMMARY OF QUANTITIES

LOCATION OF WORK:

EDGAR COUNTY
RURAL TWO LANE
ROADWAY
IMPROVEMENTS
FAP 323 (US 36)
STATION 932+29.05
TO
STATION 1682+40.00

CONSTRUCTION TYPE CODE:

I000
100% STATE
QUANTITY

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>QUANTITY</u>
40300602	SEAL COAT AGGREGATE, SPECIAL	TON	329.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	23,957.0
40600300	AGGREGATE (PRIME COAT)	TON	349.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600990	TEMPORARY RAMP	SQ YD	401.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	19,545.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	239,565.0
44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	80.0
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	393.0
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	50.0
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	440.0
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	41.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,448.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	579.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0

FILE NAME =	USER NAME = ceer-lock_jd	DESIGNED - MWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et\pwwork\pwwork\ceer-lock_jd\0124787\7014-sht-500.dgn		DRAWN -	REVISED -			323	(147,148,149)RS-4	Edgar	23	4	
PLOT SCALE = 40,0000 ' / IN.		CHECKED -	REVISED -			CONTRACT NO. 70714					
PLOT DATE = 4/9/2009		DATE -	REVISED -			SCALE: N/A	SHEET NO.	OF	SHEETS	STA.	TO STA.