

LOCATION OF WORK:	FAP 730 (US 51 BUS) NORMAL (URBAN) MCLEAN COUNTY STA 78+62.00 TO STA 209+05.20 (NB) STA 218+80.00 (SB)	FAP 730 (US 51 BUS) BLOOMINGTON (URBAN) MCLEAN COUNTY STA 209+05.20 (NB) TO STA 218+80.00 (SB) TO STA 257+00.00 (NB) STA 249+88.00 (SB)	FAP 730 (US 51 BUS) NORMAL (URBAN) MCLEAN COUNTY SN 057-0194 AT COLLEGE AVE	PARKING LANES FAP 730 (US 51 BUS) NORMAL (URBAN) MCLEAN COUNTY DRY GROVE ST TO HALE ST. (SB)	PARKING LANES, MANHOLES & INLETS FAP 730 (US 51 BUS) BLOOMINGTON (URBAN) MCLEAN COUNTY SEMINARY ST TO LOCUST ST (NB) OLIVE ST TO KENTUCKY ALLEY (SB)
-------------------	---	---	---	---	--

FUNDING BREAKOUT:	100% STATE	100% STATE	100% STATE	100% STATE	100% STATE
CONSTRUCTION TYPE CODE:	1000	1000	SFTY-2A	1000	1000

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
X0326480	SEWER REMOVAL AND REPLACEMENT SPECIAL	FOOT	150.0	0.0	0.0	0.0	0.0	150.0
X0326481	MANHOLE TO BE REMOVED AND REPLACED	EACH	2.0	0.0	0.0	0.0	0.0	2.0
X0326482	MANHOLE TO BE REMOVED AND REPLACED OVER BRICK SEWER	EACH	1.0	0.0	0.0	0.0	0.0	1.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40,000.0	20,173.0	18,682.0	0.0	227.0	918.0
40600300	AGGREGATE (PRIME COAT)	TON	800.0	403.0	374.0	0.0	5.0	18.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	8,218.0	3,727.0	4,028.0	0.0	95.0	368.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	0.5	0.5	0.0	0.0	0.0
40600990	TEMPORARY RAMP	SQ YD	9,800.0	4,998.0	4,802.0	0.0	0.0	0.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	15,448.0	6,983.0	7,892.0	75.0	95.0	403.0
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	1,030.0	1,030.0	0.0	0.0	0.0	0.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,241.0	888.0	1,353.0	0.0	0.0	0.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1,882.0	746.0	1,136.0	0.0	0.0	0.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	106,442.0	42,044.0	63,980.0	0.0	0.0	418.0
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	5,187.0	5,187.0	0.0	0.0	0.0	0.0
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	20,209.0	19,076.0	0.0	0.0	1,133.0	0.0
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	11,698.0	0.0	11,698.0	0.0	0.0	0.0
44000163	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/2"	SQ YD	16,377.0	16,377.0	0.0	0.0	0.0	0.0
44000167	HOT-MIX ASPHALT SURFACE REMOVAL, 4 1/2"	SQ YD	19,339.0	0.0	14,960.0	0.0	0.0	4,379.0
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	22,409.0	8,881.0	13,528.0	0.0	0.0	0.0
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	669.0	0.0	0.0	669.0	0.0	0.0
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	130.0	66.3	63.7	0.0	0.0	0.0
44200126	PAVEMENT PATCHING, TYPE IV, 10 INCH	SQ YD	100.0	51.0	49.0	0.0	0.0	0.0

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = bowerml	DESIGNED - GTR	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cd:\pr_work\psidot\bowerm\08128032\70775	S00.dgn	DRAWN - ML6	REVISED -					730	61,62Z,62R,62Z-1,3RS-1,2,3	MCLEAN	89	6
	PLOT SCALE = 40,0000' / IN.	CHECKED -	REVISED -		SCALE: N/A			SHEET NO. 1 OF 3 SHEETS STA. TO STA.			CONTRACT NO. 70775	
	PLOT DATE = 4/9/2009	DATE - 3/18/09	REVISED -		ILLINOIS FED. AID PROJECT							