

| | | | | |
|---------------------|---------|---------------------------|--------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1613 | 21N | SANGAMON | 46 | 4 |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

| | ITEM | UNIT | TOTAL | CONSTRUCTION TYPE CODE |
|----------|---|-------|-------|------------------------|
| | | | | 1000 100% STATE |
| 28000700 | MULCH, METHOD 1 | ACRE | 0.1 | 0.1 |
| 31101000 | SUB-BASE GRANULAR MATERIAL, TYPE B | TON | 388 | 388 |
| 35101400 | AGGREGATE BASE COURSE, TYPE B | TON | 40 | 40 |
| 35501310 | HOT-MIX ASPHALT BASE COURSE, 6 1/2" | SQ YD | 115 | 115 |
| 35501324 | HOT-MIX ASPHALT BASE COURSE, 10" | SQ YD | 884 | 884 |
| 35600716 | HOT-MIX ASPHALT BASE COURSE WIDENING, 10" | SQ YD | 80 | 80 |
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 6 | 6 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 22 | 22 |
| 40600625 | LEVELING BINDER (MACHINE METHOD), N50 | TON | 212 | 212 |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 256 | 256 |
| 40600985 | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD | 122 | 122 |
| 40600990 | TEMPORARY RAMP | SQ YD | 99 | 99 |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 337 | 337 |

* SEE SPECIAL PROVISIONS

| REVISIONS | |
|-----------|------|
| NAME | DATE |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 2 OF 4
FAS 1613 (OLD US 36) AND
FARMINGDALE ROAD (CH 15)
SECTION 21N
SANGAMON COUNTY
SCALE: VERT. NONE
HORIZ. NONE
DATE: AUGUST, 2004
DRAWN BY DJK
CHECKED BY DBS