

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1613	21N	SANGAMON	46	7
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

EARTH EXCAVATION

STATION TO STATION	EARTH EXCAVATION	EARTH EXCAV ADJUSTED FOR SHRINKAGE CU YD x 0.75	EMBANKMENT	BALANCE WASTE + BORROW (-)	CUMMULATIVE
	CU YD	CU YD	CU YD	CU YD	CU YD
OLD US 36					
STA 220+00 TO STA 224+00	115.4	86.5	34.3	52.2	52.2
TOWNSHIP ROAD 124					
STA 9+58.02 TO STA 9+75	20.2	15.1	1.0	14.1	66.3
FARMINGDALE ROAD					
STA 10+50 TO STA 12+50	117.5	88.2	154.2	(66.0)	0.3
TOTAL	253.1	189.8	189.5	0.3	
USE	253	190	190	0	

SEEDING, FERTILIZING, MULCH

STATION TO STATION	SIDE	SEEDING CLASS 2	NITROGEN FERT NUTR	PHOS FERT NUTR	POTAS FERT NUTR	AGRIC LIME	MULCH METH 2
		ACRE	LB	LB	LB	TON	ACRE
TOWNSHIP ROAD 124/ OLD US 36							
SW CORNER	LT	0.01	0.9	0.9	0.9	0.02	0.01
SE CORNER	RT	0.01	0.8	0.8	0.8	0.02	0.01
FARMINGDALE ROAD							
STA 10+00 TO STA 10+96.60	LT	0.05	4.2	4.2	4.2	0.09	0.05
STA 10+96.60 TO STA 12+50	LT	0.07	6.7	6.7	6.7	0.15	0.07
STA 10+00 TO STA 12+12.84	RT	0.07	6.4	6.4	6.4	0.14	0.07
STA 12+12.84 TO STA 12+50	RT	0.01	1.1	1.1	1.1	0.02	0.01
TOTAL		0.22	20.0	20.0	20.0	0.4	0.2
USE		0.25	21	21	21	0.4	0.25

EROSION CONTROL BLANKET

LOCATION	SIDE	QTY	DESCRIPTION
		SQ YD	
STA 220+95	34' RT	7.3	15" FLARED END SECTION
STA 221+43	34' RT	7.3	15" FLARED END SECTION
TOTAL		14.6	
USE		15	

INLET AND PIPE PROTECTION

LOCATION	SIDE	EACH
STA 220+92	34' RT	1
STA 10+72	31' LT	1
STA 11+88	31' RT	1
TOTAL		3

EROSION CONTROL

LOCATION	ESTIMATED- FOR EROSION CONTROL SEEDING	ESTIMATED- FOR EROSION CONTROL MULCH
	POUND	ACRE
FARMINGDALE ROAD		
RT	12.5	0.05
LFT	12.5	0.05
TOTAL	25.0	0.10
USE	25	0.10

TEMPORARY DITCH CHECKS

LOCATION	SIDE	EACH
TOWNSHIP ROAD 124		
STA 9+75	32' RT	1
FARMINGDALE ROAD		
STA 10+59	60' RT	1
STA 11+25	32' RT	1
STA 11+35	29' LT	1
STA 11+66	31' RT	1
STA 11+75	32' LT	1
STA 12+23	32' LT	1
STA 12+50	30' RT	1
STA 12+50	30' LT	1
TOTAL		9

PERIMETER EROSION BARRIER

LOCATION	SIDE	FOOT
TOWNSHIP ROAD		
SW CORNER	LT	31
SE CORNER	RT	24
FARMINGDALE ROAD		
STA 10+00 TO STA 10+96.60	LT	123
STA 10+96.60 TO STA 12+50	LT	18
STA 10+00 TO STA 12+12.84	RT	72
STA 12+12.84 TO STA 12+50	RT	46
TOTAL		314

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SHEET 1 OF 4
 FAS 1613 (OLD US 36) AND
 FARMINGDALE ROAD (CH 15)
 SECTION 21N
 SANGAMON COUNTY

SCALE: VERT. NONE HORIZ. NONE
 DATE: AUGUST, 2004
 DRAWN BY DJK
 CHECKED BY DBS