

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	14RS-5; 15RS-2	SCHUYLER	23	6
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SHOULDER SCHEDULE								
LOCATION			DISTANCE	HMA SHLD WIDTH	AGG SHLD WIDTH	EXCAV & GRADING EX SHLD	HMA SHLD 8 INCH	AGG SHLD TYPE B
STA	TO	STA	FOOT	FOOT	SQ YD	UNIT	SQ YD	TON
US 24 (MAINLINE )								
LT 361+70.00		LT 384+12.83	2242.83	0.0	3.0	0.0	-	106.43
LT 384+12.83		LT 384+62.83	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 384+62.83		LT 394+92.19	1029.36	3.0	3.0	10.3	343.12	48.85
LT 394+92.19		LT 395+42.19	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 395+42.19		LT 430+38.62	3496.43	0.0	3.0	0.0	-	165.92
LT 430+38.62		LT 430+88.62	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 430+88.62		LT 440+53.62	965.00	3.0	3.0	9.7	321.67	45.79
LT 440+53.62		LT 441+03.62	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 441+03.62		LT 474+92.72	3389.10	0.0	3.0	0.0	-	160.83
LT 474+92.72		LT 475+42.72	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 475+42.72		LT 489+07.86	1365.14	3.0	3.0	13.7	455.05	64.78
LT 489+07.86		LT 489+57.86	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 489+57.86		LT 536+39.04	4681.18	0.0	3.0	0.0	-	222.14
LT 536+39.04		LT 536+89.04	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 536+89.04		LT 559+54.09	2265.05	3.0	3.0	22.7	755.02	107.49
LT 563+11.59		LT 564+61.59	150.00	3.0	3.0	1.5	50.00	7.12
LT 564+61.59		LT 565+11.59	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 565+11.59		LT 666+20.64	10109.05	0.0	3.0	0.0	-	479.71
LT 666+20.64		LT 666+70.64	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 666+70.64		LT 682+49.18	1578.54	3.0	3.0	15.8	526.18	74.91
LT 682+49.18		LT 682+99.18	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 682+99.18		LT 742+81.15	5981.97	0.0	3.0	0.0	-	283.87
LT 742+81.15		LT 743+31.15	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 743+31.15		LT 746+79.13	347.98	3.0	3.0	3.5	115.99	16.51
LT 746+79.13		LT 747+29.13	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
LT 747+29.13		LT 758+63.71	1134.58	0.0	3.0	0.0	-	53.84
LT 758+63.71		LT 759+13.71	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
LT 759+13.71		LT 763+00.39	386.68	3.0	3.0	3.9	128.89	18.35
LT 1290+02.52		LT 1290+95.8	93.33	3.0	3.0	0.9	31.11	4.43
LT 1290+95.85		LT 1291+45.8	50.00	3.0	3.0	0.5	16.67	2.37
LT 1291+45.85		LT 1291+73.8	28.01	3.0	3.0	0.3	9.34	1.33
LT 1291+73.86		LT 1292+23.8	50.00	3.0	3.0	0.5	16.67	2.37
LT 1292+23.86		LT 1297+11.8	488.02	3.0	3.0	4.9	162.67	23.16
LT 1297+11.88		LT 1297+61.8	50.00	3.0	3.0	0.5	11.11	2.37
LT 1297+61.88		LT 1305+70.5	808.65	3.0	3.0	8.1	269.55	38.37
RT 30+00.00		RT 28+75.00	125.00	3.0	3.0	1.3	41.67	5.93
RT 28+75.00		RT 28+45.00	30.00	3.0	3.0	0.3	10.00	1.42
SUB-TOTAL =						104.61	3,409.14	1,969.13

SHOULDER SCHEDULE								
LOCATION			DISTANCE	HMA SHLD WIDTH	AGG SHLD WIDTH	EXCAV & GRADING EX SHLD	HMA SHLD 8 INCH	AGG SHLD TYPE B
STA	TO	STA	FOOT	FOOT	SQ YD	UNIT	SQ YD	TON
US 24 (MAINLINE )								
RT 361+70.00		RT 384+12.83	2242.83	0.0	3.0	0.0	-	106.43
RT 384+12.83		RT 384+62.83	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 384+62.83		RT 394+92.19	1029.36	3.0	3.0	10.3	343.12	48.85
RT 394+92.19		RT 395+42.19	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 395+42.19		RT 430+38.62	3496.43	0.0	3.0	0.0	-	165.92
RT 430+38.62		RT 430+88.62	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 430+88.62		RT 440+53.62	965.00	3.0	3.0	9.7	321.67	45.79
RT 440+53.62		RT 441+03.62	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 441+03.62		RT 474+92.72	3389.10	0.0	3.0	0.0	-	160.83
RT 474+92.72		RT 475+42.72	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 475+42.72		RT 489+07.86	1365.14	3.0	3.0	13.7	455.05	64.78
RT 489+07.86		RT 489+57.86	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 489+57.86		RT 536+39.04	4681.18	0.0	3.0	0.0	-	222.14
RT 536+39.04		RT 536+89.04	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 536+89.04		RT 559+54.09	2265.05	3.0	3.0	22.7	755.02	107.49
RT 563+11.59		RT 564+61.59	150.00	3.0	3.0	1.5	50.00	7.12
RT 564+61.59		RT 565+11.59	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 565+11.59		RT 666+20.64	10109.05	0.0	3.0	0.0	-	479.71
RT 666+20.64		RT 666+70.64	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 666+70.64		RT 682+49.18	1578.54	3.0	3.0	15.8	526.18	74.91
RT 682+49.18		RT 682+99.18	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 682+99.18		RT 742+81.15	5981.97	0.0	3.0	0.0	-	283.87
RT 742+81.15		RT 743+31.15	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 743+31.15		RT 746+79.13	347.98	3.0	3.0	3.5	115.99	16.51
RT 746+79.13		RT 747+29.13	50.00	3.0 TO 1.0	3.0	0.5	11.11	2.37
RT 747+29.13		RT 758+63.71	1134.58	0.0	3.0	0.0	-	53.84
RT 758+63.71		RT 759+13.71	50.00	1.0 TO 3.0	3.0	0.5	11.11	2.37
RT 759+13.71		RT 760+59.60	145.89	3.0	3.0	1.5	48.63	6.92
RT 1290+18.70		RT 1290+95.8	77.15	3.0	3.0	0.8	25.72	3.66
RT 1290+95.85		RT 1291+45.8	50.00	3.0	3.0	0.5	16.67	2.37
RT 1291+45.85		RT 1291+73.8	28.01	3.0	3.0	0.3	9.34	1.33
RT 1291+73.86		RT 1292+23.8	50.00	3.0	3.0	0.5	16.67	2.37
RT 1292+23.86		RT 1297+11.8	488.02	3.0	3.0	4.9	162.67	23.16
RT 1297+11.88		RT 1297+61.8	50.00	3.0	3.0	0.5	11.11	2.37
RT 1297+61.88		RT 1305+70.5	808.65	3.0	3.0	8.1	269.55	38.37
LT 30+00.00		LT 28+75.00	125.00	3.0	3.0	1.3	41.67	5.93
LT 28+75.00		LT 28+45.00	30.00	3.0	3.0	0.3	10.00	1.42
SUB-TOTAL =						102.04	3,323.49	1,956.94
TOTAL =						206.65	6,732.63	3,926.07

MANHOLES & WATER VALVES TO BE ADJUSTED				
STATION	DIST	SIDE	MH / WV	
29+32	14'	RT	M. H.	
29+20	20'	RT	M. H.	
28+90	16'	LT	W. V.	

REVISIONS		SHEET 2 OF 2	
NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION	
		SCHEDULE OF QUANTITIES	
		FAP 317 (US 24)	
		SECTION 14RS-5; 15RS-2	
		SCHUYLER COUNTY	
SCALE:	VERT. HORIZ.	DRAWN BY DJK	
DATE: JUNE, 2004		CHECKED BY CAJ	