

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODES		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN COLES	RURAL COLES	RURAL CUMBERLAND
				I000	I000	I000
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	138		54	84
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24800	1978	9203	13619
40600300	AGGREGATE (PRIME COAT)	TON	497	40	184	273
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	9446	582	3754	5110
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	369			369
40600895	CONSTRUCTING TEST STRIP	EACH	1			1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	847	273		574
40600990	TEMPORARY RAMP	SQ YD	646	117	120	409
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	18923	1169	7508	10246
40603520	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	739			739
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	388	37	176	175
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	11169	3910	1941	5318
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	30341	14355	7089	8897
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	31386		7090	24296
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	180105	5155	77848	97102
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1961	67	498	1396
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	319	18	15	286
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	1272	79	438	755
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4003	66	1698	2239
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1286	574	253	459
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	1	2	2
67100100	MOBILIZATION	L SUM	1	0.1	0.4	0.5
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.1	0.4	0.5
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.1	0.4	0.5
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	31552	1920	12336	17296
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94		31	63
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	227180	12898	86962	127320
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1057		605	452
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	256		256	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2629	160	872	1597
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	94		31	63
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14756		7171	7585
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1057		605	452
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	256		256	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	212424	12898	79791	119735
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1050	61	446	543
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	12		4	8

* SPECIALTY ITEMS

• COLES AND CUMBERLAND COUNTIES

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\pwwork\swartzw\d0119058\d774262-shr-soq.dgn		DRAWN -	REVISED -			116	(111,112,113-1)RS-6	•	20	3	
PLOT SCALE = 40,0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 74262					
PLOT DATE = 4/10/2009		DATE -	REVISED -			SCALE: NA	SHEET NO. 1 OF 1 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		