

ROUTE: IL 53 (Hicks Rd.)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)	HMA SURF REM 2-1/4" & RESURF	HMA SURF REM (SP) & RESURF	CLASS D PATCH TYPE I	CLASS D PATCH TYPE II	CLASS D PATCH TYPE III	CLASS D PATCH TYPE IV	PAVT MARKING 4"	RAISED REFL PAVT MKS	
FROM	TO															
US RT 12	Lake Cook Rd	NB	1	4	12	48	5				5					
		NB	1	4	12	48	5				5					
		NB	2	4	12	48	5				5					
		SB	CL	2	20	30	3		3							
		SB	2	4	6	24	3									
		SB	LT TN	4	12	48	5					5				
		SB	LT TN	4	4	16	2				2					
Lake Cook Rd	Long Grove Rd	SB	LT TN	4	4	16	2			2						
		SB	1	4	4	16	2			2						
		SB	1	4	12	48	5				5					
		SB	1	4	4	16	2			2						
		SB	CL	2	20	30	3		3							
		SB	RT EP	2	20	30	3		3							
		SB	1	4	12	48	5					5				
		SB	1	4	4	16	2				2					
		SB	1	4	4	16	2				2					
		SB	1	4	4	16	2				2					
		SB	1	12	12	144	16					16				
		SB	1	6	12	72	8					8				
		SB	1	4	4	16	2				2					
		SB	CL	2	25	38	4		4							
		Long Grove Rd	Lake Cook Rd	SB	1	6	10	60	7				7			
SB	1			6	6	36	4			4						
SB	1			6	6	36	4			4						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	1			4	4	16	2			2						
SB	CL			2	50	75	8		8							
SB	LN LI			2	200	300	33		33			33				
SB	1			4	4	16	2				2					
Lake Cook Rd	Long Grove Rd			NB	2	4	4	16	2			2				
		NB	2	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	6	6	36	4			4						
		NB	1	12	12	144	16					16				
		NB	1	6	12	72	8					8				
		NB	1	4	4	16	2			2						
Long Grove Rd	IL 83	NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	6	6	36	4			4						
		NB	1	4	10	40	4			4						
		NB	CL	2	100	150	17		17							
		NB	1	4	6	24	3			3						
		NB	1	4	10	40	4			4						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	20	80	9					9				
		NB	1	4	4	16	2			2						
		NB	1	6	6	36	4			4						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	6	6	36	4			4						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
		NB	1	4	4	16	2			2						
NB	RT TN	4	4	16	2				2							
NB	RT TN	4	12	48	5					5						

TOTALS: 0 SY 71 SY 115 SY 134 SY 350 FT 10 EACH

FILE NAME =  
 USER NAME = wilgreendp  
 PLOT SCALE = 100.0000' / IN.  
 PLOT DATE = 4/18/2008

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE  
 IL 53

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO.  
 VAR. 2008-020 PP LAKE 59 26  
 CONTRACT NO. 60E49  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT