CR003

RUNWAY 18–36

SEE TAXIWAY CENTERLINE LEAD–IN DETAIL ON THE NEXT SHEET

82.5' RADIUS

82.5' RADIUS

200'

200'

TAXIWAY "A2"

200'

EXISTING HOLDLINE TO BE REMOVED (280 S.F.)

FOR HOLDING POSITION MARKING SEE NEXT SHEET

SEE DETAIL "A" ON NEXT SHEET FOR MARKING REMOVAL

72.5' RADIUS

67.5' RADIUS (MATCH EXISTING)

PROPOSED 1' WIDE TAXIWAY STRIPE WITH 0.5' BLACK OUTLINE

MARKING NOTES

THE TAXIWAY AND APRON CENTERLINE STRIPE AND HOLDING LINE WILL BE SOLID AND YELLOW IN COLOR. THE HOLDING LINE WILL BE AS SPECIFIED IN THE DETAIL SHOWN ON THE NEXT SHEET.

ALL PROPOSED MARKING WILL BE LOCATED AS SHOWN ON THE PROPOSED MARKING SHEETS. ALL PROPOSED MARKING WILL BE APPLIED WITH A REFLECTIVE MEDIA IN ACCORDANCE WITH THE SPECIFICATIONS.

ALL PROPOSED TAXIWAY CENTERLINES WILL BE OUTLINED WITH 0.5' BLACK MARKING

CUT–OFF SHEETS WILL BE REQUIRED TO INSURE STRAIGHT EDGES.

ALL PROPOSED MARKING WILL BE PAID FOR UNDER ITEM:
AR620520 "PAVEMENT MARKING–WATERBORNE" – PER SQ. FT.

LEGEND

- EXISTING PAVEMENT
- PROPOSED PAVEMENT
- EXISTING MARKING
- EXISTING MARKING TO BE REMOVED
- PROPOSED MARKING

MATCHLINE STA. 33+00

MATCHLINE STA. 41+00

TAXIWAY "A"

TAXIWAY "A"

MATCHLINE STA. 41+00

MATCHLINE STA. 49+00

PROPOSED 1' WIDE TAXIWAY STRIPE WITH 0.5' BLACK OUTLINE

TAXIWAY "A"

0' 15' 30' 60'
FULL SIZE SCALE: 1"= 30'
HALF SIZE SCALE: 1"= 60'

DATE	REVISION	BY

CARMI MUNICIPAL AIRPORT
CARMI, ILLINOIS

A.I.P. PROJ.: 3-17-0109-B7

IL PROJ.: CUL-3683

HSI Project No.: 801-07TXYD 0800
Filename: R-151MRK.DWG
Scale: 1"=30'
Date: 02/16/07

LAYOUT	MDR	02/16/07
DRAWN	MDR	02/16/07
REVIEWED	CAH	03/27/07

HANSON

Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

EXTEND PARTIAL PARALLEL TAXIWAY

PROPOSED MARKING PLAN STA. 33+00 TO STA. 49+00

17

17 of 55 sheets

APR 27, 2007 7:41 AM BAK
I:\AIRPORTS\CARMI\801-07TXY\AIRPORT\SHEETS\R-151MRK.DWG – STA. 33+00 TO STA.49+00