


DATE	REVISION	BY


SUMMARY OF QUANTITIES				
ITEM No.	DESCRIPTION	UNIT	QUANTITIES	AS-BUILT QTYS.
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	2,650	
AR152511	SUBGRADE REPAIR	S.Y.	500	
AR156531	EROSION CONTROL BLANKET	S.Y.	3,270	
AR201610	BITUMINOUS BASE COURSE	TON	3,035	
AR201630	BITUMINOUS BASE TEST SECTION	EACH	1	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	500	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	100	
AR401610	BITUMINOUS SURFACE COURSE	TON	1,825	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	20,215	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	1,025	
AR510510	TIE DOWN	EACH	19	
AR510515	GROUND ROD	EACH	3	
AR510900	REMOVE TIE DOWN	EACH	25	
AR603510	BITUMINOUS TACK COAT	GAL.	5,050	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	6,675	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	4,650	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	775	

INDEX TO SHEETS	
SHEET No.	SHEET DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED SAFETY PLAN
5	PROPOSED HAUL ROUTE
6	PROPOSED PAVEMENT PREPARATION PLAN - STA. 150+50 TO STA. 164+25
7	PROPOSED PAVEMENT PREPARATION PLAN - STA. 164+25 TO STA. 170+54
8	PROPOSED CONSTRUCTION PLAN - STA. 150+50 TO STA. 164+25
9	PROPOSED CONSTRUCTION PLAN - STA. 164+25 TO STA. 170+54
10	PROPOSED STORMWATER POLLUTION PREVENTION PLAN - STA. 150+50 TO STA. 164+25
11	PROPOSED STORMWATER POLLUTION PREVENTION PLAN - STA. 164+25 TO STA. 170+54
12	PROPOSED PLAN & PROFILE - STA. 150+50 TO STA. 164+25
13	PROPOSED PLAN & PROFILE - STA. 164+25 TO STA. 170+54
14	PROPOSED PAVEMENT MARKING PLAN - STA. 150+50 TO STA. 164+25
15	PROPOSED PAVEMENT MARKING PLAN - STA. 164+25 TO STA. 170+54
16	TAXIWAY "A" EXISTING AND PROPOSED TYPICAL SECTIONS
17	TAXIWAY "A" PROPOSED CROSS-SECTIONS - STA. 150+94.80 TO STA. 154+50
18	TAXIWAY "A" PROPOSED CROSS-SECTIONS - STA. 155+00 TO STA. 159+00
19	TAXIWAY "A" PROPOSED CROSS-SECTIONS - STA. 159+50 TO STA. 163+50
20	TAXIWAY "A" PROPOSED CROSS-SECTIONS - STA. 164+00 TO STA. 168+00
21	TAXIWAY "A" PROPOSED CROSS-SECTIONS - STA. 168+50 TO STA. 170+54
22	GENERAL AVIATION APRON EXISTING AND PROPOSED TYPICAL SECTIONS
23	GENERAL AVIATION APRON PROPOSED CROSS-SECTIONS - STA. 2158+11 TO STA. 2159+00
24	GENERAL AVIATION APRON PROPOSED CROSS-SECTIONS - STA. 2159+50 TO STA. 2160+50
25	GENERAL AVIATION APRON PROPOSED CROSS-SECTIONS - STA. 2161+00 TO STA. 2162+50
26	GENERAL AVIATION APRON PROPOSED CROSS-SECTIONS - STA. 2163+00 TO STA. 2163+21

APR 17, 2008 4:01 PM HARRI01115
E:\AIRPORTS\DECATUR\07A0169\CADD\AIRPORT\SHEET\R-002ELP.DWG - Quantity Summary



HEC Project No.	07A0169D_0802
Revision	R-002ELP.DWG
Scale	N/A
Date	04/18/08
LAYOUT	MLH 03/19/08
DRAWN	MLH 03/19/08
REVIEWED	JDW 04/17/08



RECONSTRUCT
TAXIWAY "A" AND
ADJACENT GA APRON
SUMMARY OF QUANTITIES
AND INDEX TO SHEETS