

MARKING REMOVAL NOTES

THE AREAS THAT ARE DESIGNATED EXISTING MARKING (TO BE REMOVED) WILL BE REMOVED BY WATER BLASTING, SANDBLASTING, OR SHOT BLASTING.

AREAS TO BE REMOVED ARE CALLED OUT ON THE PROPOSED MARKING PLAN SHEETS.

ALL AREAS TO BE REMOVED ARE CALCULATED AREAS. ANY ADDITIONAL AREAS, DUE TO OVER SPRAY, SHALL BE CONSIDERED INCIDENTAL TO THE CONTRACT AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ALL MARKING REMOVAL ITEMS WILL BE PAID FOR AS FOLLOWS:
AR620800 "PAVEMENT MARKING REMOVAL" - PER SQ. FT.

MARKING NOTES

ALL PROPOSED MARKING WILL BE LOCATED AS SHOWN ON THE PROPOSED MARKING PLAN SHEETS.

ALL RUNWAY MARKING WILL BE SOLID AND WHITE IN COLOR.

ALL TAXIWAY MARKING WILL BE SOLID AND YELLOW IN COLOR.

ALL YELLOW & WHITE PROPOSED MARKING WILL HAVE A REFLECTIVE MEDIA APPLIED IN ACCORDANCE WITH THE SPECIFICATIONS.

ALL PROPOSED MARKING WILL BE OUTLINED WITH A 6" WIDE (BLACK) OUTLINE STRIPE.

ALL PROPOSED MARKING LOCATED ON PROPOSED OR EXISTING CONCRETE WILL REQUIRE WATER, SAND OR SHOT BLASTING PRIOR TO INSTALLATION TO REMOVE ANY CURING COMPOUND. THIS DOES NOT APPLY TO MARKING ALREADY IN PLACE. BITUMINOUS AREAS ARE DESIGNATED ON THESE PROPOSED MARKING PLANS. THIS WILL BE A PART OF THE PROPOSED PAVEMENT MARKING AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

CUT-OFF SHEETS WILL BE REQUIRED TO INSURE STRAIGHT EDGES.

ALL PROPOSED MARKING ITEMS WILL BE PAID FOR AS FOLLOWS:
AR620520 "PAVEMENT MARKING-WATERBORNE" - PER SQ. FT.


ALL PROPOSED BLACK MARKING ITEMS WILL BE PAID FOR AS FOLLOWS:
AR620525 "PAVEMENT MARKING-BLACK BORDER" - PER SQ. FT.

MARKING QUANTITIES	
YELLOW MARKING: AR620520	TOTAL AREA (S.F.)
TAXIWAY CENTERLINES & LEAD-IN STRIPES	1,333
TOTAL YELLOW:	1,333
WHITE MARKING: AR620520	TOTAL AREA (S.F.)
RUNWAY THRESHOLD STRIPE - 5.75'x150' (x8)	6,900
RUNWAY CENTERLINE STRIPE - 3'x120' (x24)	8,640
RUNWAY AIMING POINT STRIPE - 20'x150' (x4)	12,000
RUNWAY NUMERAL 1 (x2)	640
RUNWAY NUMERAL 2	652
RUNWAY NUMERAL 9	735
TOTAL WHITE:	29,567
TOTAL MARKING:	30,900
BLACK MARKING: AR620525	TOTAL AREA (S.F.)
TAXIWAY CENTERLINE	1,332
RUNWAY THRESHOLD STRIPE - (x8)	1,256
RUNWAY CENTERLINE STRIPE - (x24)	2,976
RUNWAY AIMING POINT STRIPE - (x4)	684
RUNWAY NUMERAL 1 (x2)	135
RUNWAY NUMERAL 2	108
RUNWAY NUMERAL 9	114
TOTAL BLACK:	6,605

MARKING REMOVAL QUANTITIES	
EXISTING MARKING: AR620900	TOTAL AREA (S.F.)
TAXIWAY CENTERLINE	508
RUNWAY AIMING POINT STRIPE	3,300
THRESHOLD STRIPE	3,000
TOTAL REMOVAL:	6,808

LEGEND

	PAVEMENT EDGE
	EXISTING MARKING
	PROPOSED MARKING




REVISION	DATE	BY

EFFINGHAM COUNTY
MEMORIAL AIRPORT
EFFINGHAM, ILLINOIS

IL. PROJ.: 1H2-3761 A.L.P. PROJ.: 3-17-0040-811

HE Project No. 07A0143D_0800			
Planets R-151MRK.DWG			
Scale 1" = 50'			
Date 02/12/08			
LAYOUT	CCC	01/21/08	
DRAWN	CCC	01/21/08	
REVIEWED	CAH	02/12/08	



WIDEN RUNWAY 11/29
AND REPLACE MIL'S
PROPOSED
MARKING PLAN
STA. 160+00 TO STA. 147+00

APR 09, 2008 6:44 PM HAGL000382
I:\ARPCRS\EFFINGHAM\07A0143\CAD\SHEETS\R-151MRK.DWG - CONST 1