


PE086

**GREATER PEORIA REGIONAL AIRPORT
CONSTRUCT NEW PERIMETER ROAD AND PERIMETER FENCE - PROJECT 1
FINAL ENGINEER'S OPINION OF PROBABLE CONSTRUCTION COST**

Item #	Description	Unit	Quantity	Approved Revisions
AR108158	1/C #8 5KV UG Cable in UD	LF	550	
AR110014	4" Directional Bore	LF	140	
AR110501	1-Way Conc. Encased Duct	LF	40	
AR125415	MITL-Base Mounted	EA	2	
AR125420	Taxiway Light Inpavement	EA	3	
AR125902	Remove Base Mounted Light	EA	10	
AR125904	Remove Taxi Guidance Sign	EA	1	
AR151450	Clearing and Grubing	AC	1.3	
AR152410	Unclassified Excavation	CY	78,875	
AR156510	Silt Fence	LF	6,176	
AR156511	Ditch Check	EA	16	
AR156512	Bales	EA	136	
AR162510	Class E Fence 10'	LF	11,650	
AR162604	Class E Gate - 4'	EA	1	
AR162624	Class E Gate - 24'	EA	1	
AR162626	Class E Gate - 26'	EA	1	
AR162718	Electrical Gate - 18'	EA	3	
AR162724	Electrical Gate - 24'	EA	2	
AR162900	Remove Class E Fence	LF	11,440	
AR162908	Remove Electric Gate	EA	4	
AR162910	Remove Class E Gate	EA	5	
AR201610	Bituminous Base Course	TON	3,525	
AR201630	Bituminous Base Test Section	EA	1	
AR209612	Crushed Aggregate Base Coarse - 12"	SY	31,802	
AR401610	Bituminous Surface Course	TON	3,410	
AR401630	Bituminous Surface Test Section	EA	1	
AR401900	Remove Bituminous Pavement	SY	11,515	
AR602510	Bituminous Prime Coat	GAL	9,517	
AR603510	Bituminous Tack Coat	GAL	2,600	
AR620510	Pavement Marking	SF	17,312	
AR701512	12" RCP, Class IV	LF	125	
AR701515	15" RCP, Class IV	LF	415	
AR701518	18" RCP, Class IV	LF	608	
AR701524	24" RCP, Class IV	LF	511	
AR701530	30" RCP, Class IV	LF	168	
AR701536	36" RCP, Class IV	LF	52	
AR701719	RCEP Span 38" Rise 24"	LF	141	
AR701900	Remove Pipe	LF	241	
AR751410	Inlet	EA	19	
AR751560	Manhole 6'	EA	2	
AR751567	Manhole 7'	EA	2	
AR751900	Remove Inlet	EA	2	
AR752412	Precast Reinforced Concrete FES 12"	EA	4	
AR752424	Precast Reinforced Concrete FES 24"	EA	1	
AR752730	Precast Reinforced Concrete FES Eq. Round Size 30"	EA	2	
AR752900	Remove End Section	EA	13	
AR754410	Comb. Concrete Curb and Gutter	LF	395	
AR754904	Remove Comb. Curb and Gutter	LF	570	
AR800353	Access Controls	L.S.	1	
AR800396	Gate Operator Modifications	EA	1	
AR800397	Temporary Fence	L.S.	1	
AR800399	6" High Concrete Median	S.Y.	6	
AR901510	Seeding	AC	16.0	
AR908510	Mulching	AC	16.0	
AR910200	Roadway Sign	EA	5	
AR910400	Guardrail	LF	1,775.0	


REVISIONS		
NUMBER	BY	DATE

0 1 2
THIS BAR IS EQUAL TO 2'
AT FULL SCALE (3-40222)
PLOT 1



GREATER Peoria REGIONAL Airport

CONSTRUCT NEW PERIMETER ROAD AND PERIMETER FENCE - PROJECT 1



CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
Copyright CMT, Inc.

FILE#	\$FILE\$
DESIGN BY:	CET
DRAWN BY:	CMT
CHECKED BY:	XXX
APPROVED BY:	XXX
DATE:	10-26-2007
JOB No:	0706104

SUMMARY OF QUANTITIES
SHEET 2 OF 140 SHEETS

K:\Peoria\070610400\Draw\Sheets
FILE: 002_Summary_of_Quantities.dwg
DATE: 4/24/2008 2:21 PM