

# TRANSPORTATION BULLETIN



Illinois Department of Transportation

## ADDENDUM NO. 1

Dated: May 5, 2008

For: Transportation Bulletin  
Volume 11, No. 16, Dated: April 18, 2008

Letting Date: May 16, 2008 Special Letting

### ITEM 8A

QUAD CITY INTERNATIONAL AIRPORT  
MOLINE, ILLINOIS  
ILL. PROJ. MLI-3790  
A.I.P. NO. 3-17-0068-XX  
CONTRACT NO. QU006

### REASON FOR ADDENDUM:

To change the sanitary sewer pipe size from 8" Diameter to 10" Diameter and to add additional requirements regarding inspection and acceptance of sanitary sewer installation.

### TO ALL PLAN HOLDERS:

1. CONSTRUCTION PLAN SHEET 2:

DELETE: Item AR770508, 8" Sanitary Sewer 1,288 L.F.

ADD: Item AR770510, 10" Sanitary Sewer 1,288 L.F.

2. CONSTRUCTION PLAN SHEET 21:

DELETE: 1,288 L.F. of 8" Dia., D.I.P. CL 350 Sanitary Sewer between Manhole 25 and Manhole 30.

ADD: 1,288 L.F. of 10" Dia., D.I.P. CL 350 Sanitary Sewer between Manhole 25 and Manhole 30.

3. SECTION III SPECIAL PROVISIONS, PAGE 69, ITEM 770-1.2, FIRST PARAGRAPH, SECOND LINE:

CHANGE: "Item AR770508--8" Sanitary Sewer" to "AR770510--10" Sanitary Sewer".

4. SECTION III SPECIAL PROVISIONS, PAGE 72, ITEM 770-2.2:

ADD:

This work shall be performed by the Contractor and witnessed by the City in accordance with applicable sections of the Standard Specifications for Water & Sewer Main Construction in Illinois.

All sanitary sewers will receive a TV inspection and all manholes will receive a visual inspection by Water Pollution Control personnel prior to final City acceptance. The initial inspection will be done at no charge to the Contractor. Any required TV re-inspection will be charged at a fee of \$100 per hour. Said fee will be deducted from the payment due the Contractor.

5. SECTION III SPECIAL PROVISIONS, PAGE 75, ITEM 770-4.2, FIRST LINE UNDER "PAYMENT WILL BE MADE UNDER":

CHANGE: "Item AR770508--8" Sanitary Sewer" to "AR770510--10" Sanitary Sewer".

6. PROPOSAL, between pages 6 and 7:

Replace the "Schedule of Prices" with the revised "Schedule of Prices" included herein.

STATE JOB # - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - QU006

ECMS002 DTGECM03 ECMR003 PAGE 1  
 RUN DATE - 05/01/08  
 RUN TIME - 215750

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
ROCK ISLAND	161	02	QUAD-CITY INTERNATIONAL	3-17-0068-XX	ML-I -3790

\*\*\*\*\* BASE \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR107920	REPLACE WIND CONE	EACH	1.000 X		=		
AR108658	3/C #8 600 V UG CABLE IN UD	L.F.	700.000 X		=		
AR110214	4" STEEL DUCT, DIRECT BURY	L.F.	95.000 X		=		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000 X		=		
AR150530	TRAFFIC MAINTENANCE	L.S.	1.000 X		=		
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	236,000.000 X		=		
AR152441	ON-SITE BORROW	C.Y.	60,800.000 X		=		
AR152515	SUBGRADE UNDERCUT	C.Y.	13,435.000 X		=		
AR152540	SOIL STABILIZATION FABRIC	S.Y.	11,710.000 X		=		
AR156500	TEMPORARY EROSION CONTROL	L.S.	1.000 X		=		
AR156543	RIPRAP-GRADATION NO. 3	S.Y.	7,500.000 X		=		
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	5,360.000 X		=		
AR209511	CRUSHED AGGREGATE BASE, (CA-1)	TON	100.000 X		=		
AR209600	GEOTEXTILE FABRIC	S.Y.	4,400.000 X		=		
AR701430	30" RCP, CLASS III	L.F.	168.000 X		=		



QUAD-CITY INTERNATIONAL  
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - QU006

ECMS002 DTGECM03 ECMR003 PAGE 2  
 RUN DATE - 05/01/08  
 RUN TIME - 215750

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR701442	42" RCP, CLASS III	L.F.	218.000 X		=		
AR701512	12" RCP, CLASS IV	L.F.	350.000 X		=		
AR701515	15" RCP, CLASS IV	L.F.	272.000 X		=		
AR701518	18" RCP, CLASS IV	L.F.	467.000 X		=		
AR701524	24" RCP, CLASS IV	L.F.	705.000 X		=		
AR701710	RCEP SPAN 23 RISE 14	L.F.	213.000 X		=		
AR701713	RCEP SPAN 30 RISE 19	L.F.	366.000 X		=		
AR701719	RCEP SPAN 38 RISE 24	L.F.	790.000 X		=		
AR701900	REMOVE PIPE	L.F.	75.000 X		=		
AR705508	8" PERFORATED UNDERDRAIN	L.F.	820.000 X		=		
AR705610	CONCRETE HEADWALL FOR UNDERDRAIN	EACH	25.000 X		=		
AR751410	INLET	EACH	4.000 X		=		
AR751411	INLET-TYPE A	EACH	1.000 X		=		
AR751415	INLET-SPECIAL	EACH	1.000 X		=		
AR751540	MANHOLE 4'	EACH	3.000 X		=		

QUAD-CITY INTERNATIONAL  
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - QU006

ECMS002 DTGECM03 ECMR003 PAGE 3  
 RUN DATE - 05/01/08  
 RUN TIME - 215750

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR751550	MANHOLE 5'	EACH	1.000 X		=		
AR751560	MANHOLE 6'	EACH	1.000 X		=		
AR751903	REMOVE MANHOLE	EACH	3.000 X		=		
AR752424	PRECAST REINFORCED CONC. FES 24"	EACH	6.000 X		=		
AR752442	PRECAST REINFORCED CONC. FES 42"	EACH	2.000 X		=		
AR752524	GRATING FOR CONC. FES 24"	EACH	2.000 X		=		
AR752730	P R CONC. FES EQ. ROUND SIZE 30"	EACH	1.000 X		=		
AR770510	10" SANITARY SEWER	L.F.	1,288.000 X		=		
AR770704	SANITARY MANHOLE 4'	EACH	2.000 X		=		
AR770925	REPLACE SANITARY MANHOLE	EACH	1.000 X		=		
AR801604	SETTLEMENT PLATES	EACH	10.000 X		=		
AR901510	SEEDING	ACRE	109.000 X		=		
AR908513	MULCHING-METHOD 3	ACRE	109.000 X		=		
AR908520	EXCELSIOR BLANKET	S.Y.	1,500.000 X		=		

SUBTOTAL BASE \$

\*\*\*THE DEPARTMENT RESERVES THE RIGHT TO AWARD THIS CONTRACT ON THE  
 \*\*\*BASIS OF ANY OF THE ALTERNATES OR COMBINATION THEREOF.

QUAD-CITY INTERNATIONAL  
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - QU006

ECMS002 DTGECM03 ECMR003 PAGE 4  
 RUN DATE - 05/01/08  
 RUN TIME - 215750

\*\*\*\*\* ALT 1 \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AS152420	COMMON EXCAVATION	C.Y	12,002.000 X			=	
AS901510	SEEDING	ACRE	3.000 X			=	
AS908513	MULCHING - METHOD 3	ACRE	3.000 X			=	
				SUBTOTAL ALT 1		\$	



QUAD-CITY INTERNATIONAL  
 ROCK ISLAND

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT NUMBER - QU006

ECMS002 DTGECM03 ECMR003 PAGE 5  
 RUN DATE - 05/01/08  
 RUN TIME - 215750

\*\*\*\*\* ALT 2 \*\*\*\*\*

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AT152420	COMMON EXCAVATION	C.Y.	30,366.000 X			=	
AT901510	SEEDING	ACRE	3.000 X			=	
AT908513	MULCHING - METHOD 3	ACRE	3.000 X			=	

SUBTOTAL ALT 2 \$ 

--	--

  
 CONTRACT - QU006

SUMMARY OF TOTAL ALTERNATES		
	DOLLARS	CTS
TOTAL BASE \$		
TOTAL ALT 1 \$		
TOTAL ALT 2 \$		

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.