

Index to Sheets

Sheet Number	Description
1	Cover Sheet
2	Index to Sheets and Summary of Quantities
3	Site Plan
4	General Notes and Details
5	Horizontal and Vertical Controls
6	Construction Activity General Notes and Details
7	Construction Activity Plan Phase 1 Overview
8	Construction Activity Plan Phase 1 Detailed View
9	Construction Activity Plan Phase 2
10	Construction Activity Plan Additive Alternate 1
11	Enhanced Centerline Marking Work Areas
12	Enhanced Centerline Marking Construction Activity Plan Phase 1
13	Enhanced Centerline Marking Construction Activity Plan Phase 2
14	Enhanced Centerline Marking Construction Activity Plan Phase 3
15	Enhanced Centerline Marking Construction Activity Plan Phase 4
16	Enhanced Centerline Marking Construction Activity Plan Phase 5
17	Enhanced Centerline Marking Construction Activity Plan Phase 6
18	Existing Conditions and Removals - Apron
19	Existing Conditions and Removals - Taxiway A6 & A7
20	Pavement Removal Details Sheet 1
21	Pavement Removal Details Sheet 2
22	Pavement Removal Details Sheet 3
23	Pavement Removal Details Sheet 4
24	Project Improvements - Apron
25	Project Improvements - Taxi and Limousine Waiting Area
26	Project Improvements - Taxiway A6 & A7
27	New Typical Sections - Apron
28	New Typical Sections - Taxiway A6 & A7
29	Jointing Plan - Apron
30	New Jointing Details
31	Paving and Miscellaneous Details Sheet 1
32	Paving and Miscellaneous Details Sheet 2
33	Paving at In-Pavement Structures and Crack Sealing Details
34	Sidewalk and Curb Details
35	Staking Plan 1 - Apron
36	Staking Plan 2 - Sidewalk and Curb & Taxi and Limo Drive
37	Staking Plan 3 - Taxiway A6 & A7
38	Underdrain Plan
39	Underdrain Details
40	Marking and Ground Rod Plan
41	Terminal Area Marking Plan and Parking Block Layout
42	Enhanced Taxiway Centerline Marking Details
43	Fencing Plan
44	Fence Details
45	Electrical Gate Details Sheet 1
46	Electrical Gate Details Sheet 2
47	Electrical Gate Details Sheet 3
48	Electrical Adjustments & Details Sheet 1
49	Electrical Adjustments & Details Sheet 2
50	Grading, Turfing & Erosion Control Plan
51	Erosion Control Details
52	Index to Cross Sections
53	Cross Sections - Apron Sheet 1 - Baseline C Sta. 24+50.14 to Sta. 28+50
54	Cross Sections - Apron Sheet 2 - Baseline C Sta. 29+00 to Sta. 29+50.22
55	Cross Sections - Taxiway A7 - Sta. 95+50 to Sta. 99+50
56	Cross Sections - Additive Alternate 1 - Taxiway A6 Sheet 1 - Sta. 95+50 to Sta. 99+00
57	Cross Sections - Additive Alternate 1 - Taxiway A6 Sheet 2 - Sta. 99+50


Summary of Quantities

Item Number	Description	UNIT	QUANTITY
BASE BID - REHABILITATE AIR CARRIER APRON, PHASE 2, REHABILITATE TAXIWAY A7, AND ENHANCED CENTERLINE MARKINGS			
AR110949	Adjust Cable Marker	EA	8
AR125941	Adjust Stake Mounted Light	EA	6
AR125942	Adjust Base Mounted Light	EA	4
AR125944	Adjust Taxi Guidance Sign	EA	1
AR150510	Engineer's Field Office	LS	1
AR152410	Unclassified Excavation	CY	800
AR152480	Shoulder Adjustment	SY	2,900
AR156510	Silt Fence	LF	1,200
AR156513	Separation Fabric	SY	6,575
AR156520	Inlet Protection	EA	5
AR162408	Class E Fence, Vinyl-8'	LF	835
AR162720	Electric Gate - 20'	EA	1
AR162900	Remove Class E Fence	LF	830
AR162908	Remove Electric Gate	EA	1
AR163000	Temporary Construction Fence	LF	360
AR201610	Bituminous Base Course	TON	400
AR201661	Clean and Seal Bituminous Cracks	LF	600
AR209608	Crushed Aggregate Base Course - 8"	SY	6,575
AR302900	Remove 4" ATPS	SY	6,115
AR401610	Bituminous Surface Course	TON	525
AR401655	Butt Joint Construction	SY	470
AR401900	Remove Bituminous Pavement	SY	1,795
AR501508	8" PCC Pavement	SY	6,115
AR501530	PCC Test Batch	EA	1
AR501604	4" PCC Sidewalk	SF	1,120
AR501690	PCC Sidewalk Removal	SF	1,120
AR501908	8" PCC Pavement Removal	SY	6,115
AR510515	Ground Rod	EA	5
AR510905	Remove Ground Rod	EA	5
AR602510	Bituminous Prime Coat	GAL	200
AR603510	Bituminous Tack Coat	GAL	1,100
AR620510	Pavement Marking	SF	16,500
AR705524	4" Perforated Underdrain w/Sock	LF	480
AR754210	Concrete Curb	LF	170
AR754410	Comb. Concrete Curb & Gutter	LF	115
AR754900	Remove Concrete Curb	LF	240
AR754904	Remove Comb. Concrete Curb & Gutter	LF	115
AR800215	Remove Bollard	EA	5
AR800283	Clean and Repaint Bollard	EA	12
AR800284	Remove, Repaint and Reinstall Guardrail	LF	150
AR800285	Remove Parking Block	EA	15
AR800390	PCC Joint Milling	LF	3,450
AR800391	PCC Partial Depth Patch	LF	3,450
AR800420	Reflective Crack Control - ISAC	LF	3,450
AR901510	Seeding	AC	1
AR904510	Sodding	SY	650
AR908510	Mulching	AC	1
AR910410	Parking Block	EA	15
AR910420	Bollard	EA	5
ADDITIVE 1 - REHABILITATE TAXIWAY A6			
AS110949	Adjust Cable Marker	EA	4
AS125941	Adjust Stake Mounted Light	EA	6
AS125942	Adjust Base Mounted Light	EA	4
AS125944	Adjust Taxi Guidance Sign	EA	1
AS152480	Shoulder Adjustment	SY	2,500
AS156510	Silt Fence	LF	825
AS156520	Inlet Protection	EA	1
AS201610	Bituminous Base Course	TON	475
AS201661	Clean and Seal Bituminous Cracks	LF	600
AS401610	Bituminous Surface Course	TON	525
AS401655	Butt Joint Construction	SY	650
AS401900	Remove Bituminous Pavement	SY	475
AS603510	Bituminous Tack Coat	GAL	1,000
AS620510	Pavement Marking	SF	3,145
AS705944	Adjust Underdrain Cleanout	EA	1
AS800390	PCC Joint Milling	LF	2,400
AS800391	PCC Partial Depth Patch	LF	2,400
AS800420	Reflective Crack Control - ISAC	LF	2,400
AS901510	Seeding	AC	0.5
AS904510	Sodding	SY	350
AS908510	Mulching	AC	0.5

K:\Champaign\030590302 Apron Rehab 2\Draw\S
 FILE: INDEXSUM.dwg
 UPDATE BY: Sean Smith
 PLOT DATE: 4/18/2008 9:42 AM

REVISIONS

NUMBER	BY	DATE



UNIVERSITY OF ILLINOIS
 WILLARD AIRPORT
 REHABILITATE AIR CARRIER RAMP, PHASE 2
 INDEX TO SHEETS
 AND
 SUMMARY OF QUANTITIES

© Copyright CMT, Inc.
CMT
 CRAWFORD, MURPHY & TULLY, INC.
 CONSULTING ENGINEERS
 License No. 84-00063

DESIGN BY: SMS
 DRAWN BY: CMT
 CHECKED BY: *gms*
 APPROVED BY: *gms*
 DATE: 04/18/2008
 JOB No: 0305903
 CMI-3663
 3-17-0016-XX
 SHEET 02 OF 57 SHEETS