


SECONDARY GATE OPERATOR ENTRAPMENT PROTECTION CONTACT SENSORS

N.T.S.



DETECTOR LOOP DETAILS

CAUTION:


- . DO NOT SPLICE WIRE.
- DO NOT FRACTURE WIRE INSULATION. LOOPS SHORTED TO GROUND WILL CAUSE DETECTOR MALFUNCTION. WHEN PLACING WIRE IN THE SLOT, DO NOT USE SCREWDRIVER OR OTHER SHARP TOOLS.

TYPICAL LAYOUT FOR LOOP:

- SAW SLOT 3/16" WIDE x 1-1/2" DEEP. MAKE RECTANGULAR SHAPE TO SPECIFIED LOOP DIMENSIONS PLUS SLOT FOR LEAD CONDUIT.
- GROUT WITH NO. 202 WEATHERBAN SEALANT (A PRODUCT OF 3M CO.) OR APPROVED EQUIVALENT ... (EXAMPLE: DE WITTS NO. 99 BLACK MASTIC CAULK).

- 1.) LOOP LEADS ARE LIMITED TO 100 FEET.
- 2.) LOOP LEADS MUST HAVE FOUR (4) TWISTS PER FOOT.
- 3.) LOOP AND LOOP LEADS MUST BE LOCATED, AT LEAST, 18" FROM ANY ELECTRICAL POWER SERVICE OR RUN, OR STEEL REINFORCEMENT.
- 4.) LOOP LEADS MUST BE IN SEPERATE CONDUIT BETWEEN LOOP AND DETECTOR. THEY MUST NOT SHARE CONDUIT WITH OTHER WIRING OR LEADS FROM OTHER LOOPS.
- 5.) WIRE SHALL BE #16 THHN SINGLE CONDUCTOR STRANDED WIRE.
- 6.) ALL WIRE SHALL BE CONTINOUS WITHOUT SPLICING.

LOCATIONS, DETAILS AND CHARACTER OF EQUIPMENT SHOWN ON THIS SHEET ARE GENERIC. EQUIPMENT LOCATION SHALL BE AS RECOMMENDED BY THE EQUIPMENT MANUFACTURER.



TOP PRIMARY MEMBER

STANDARD TRACK (TYP.)

GATE FRAME SECTION

N.T.S.

SUMMARY OF OPERATION

- 1.) THE GATES SHALL HAVE AN AUTOMATIC GATE OPERATOR WITH TWO CARD READERS AND REMOTE CONTROL. ONCE THE GATE IS OPENED IT WILL REMAIN OPEN FOR THE TIME SPECIFIED BY THE OWNER AFTER THE LOOP PICKUPS DETERMINE THAT THERE ARE NO VEHICLES OVER THE PICKUP LOOPS.
- ACTUATING THE GATE OPENERS VIA THE CARD READER REQUIRES THE VEHICLE TO APPROACH THE GATE ENTRANCE AND STOP. THE DRIVER ACTIVATES THE GATE OPENER BY SWEEPING HIS CARD. THE ACCESS CONTROL DEVICE TRANSMITS AN IMPULSE TO ACTIVATE THE GATE OPENER TO OPEN THE GATE. AFTER THE GATE IS FULLY OPENED AND STOPPED, THE VEHICLE PROCEEDS THROUGH THE OPENING, PASSING OVER THE LOOPS. WHILE THE VEHICLE IS IN THE LOOP SENSING RANGE, AN IMPULSE IS TRANSMITTED TO THE GATE OPERATOR TO HOLD THE GATE IN THE OPEN POSITION. WHEN THE LOOP HAS BEEN CLEARED, THE AUTOMATIC TIMER IS ACTIVATED AND, WHEN THE USER-DETERMINED TIME HAS ELAPSED, IT WILL ACTIVATE THE GATE OPENER TO CLOSE THE GATE. EXITING THE AREA IS ACCOMPLISHED IN THE SAME MANNER.

R SHAL	,		. SIGNS A	\S INDICATED IN TABLE BELOW	OF ILLINOIS
	BACKGROUND LETTERING				>-0
ISIONS	COLOR	COLOR	HEIGHT	TEXT	
x 18"	WHITE	RED	1.5"	FAA REGULATIONS REQUIRE	
				THAT AFTER ENTERING OR	ERSI
				EXITING THROUGH THIS	
				SECURITY GATE YOU ARE	>2
				REQUIRED TO WAIT UNTIL THE	₹^
				GATE CLOSES BEFORE	5
				PROCEEDING, FINES OR	
				PENALTIES WILL BE IMPOSED.	
_	SEE	WARNIN	IG SIGN I	DETAIL	

CONTRACTOR

DIMEN

SIGN

1) SIGNS #1 AND #3 SHALL BE INSTALLED ON BOTH SIDES OF GATE. SIGN #2 SHALL BE INSTALLED ON "LAND" SIDE OF GATE.

UL 235 COMPLIANCE NOTES

GATE INSTALLATION SHALL COMPLY WITH ALL REQUIREMENTS OF UL 235. INCLUDING, BUT NOT LIMITED TO:

- ALL OPENINGS OF THE SLIDE GATE ARE GUARDED OR SCREENED FROM THE BOTTOM OF THE GATE TO A MINIMUM OF 4 FEET ABOVE GROUND TO PREVENT A 2-1/4" DIAMETER SPHERE FROM PASSING THROUGH THE OPENINGS ANYWHERE IN THE GATE, AND IN THAT PORTION OF THE ADJACENT FENCE THAT THE GATE COVERS IN THE OPEN POSITION.
- ALL EXPOSED PINCH POINTS ARE ELIMINATED OR GUARDED AND GUARDING IS SUPPLIED FOR ALL EXPOSED ROLLERS.
- A WARNING SIGN (SEE DETAIL, THIS SHEET) MUST BE AFFIXED TO BOTH SIDES OF THE SLIDE GATE.
- FOR ADDITIONAL UL 235 REQUIREMENTS FOR THIS GATE INSTALLATION, SEE GATE OPERATOR DETAILS SHEET.

CANTORD, CMT DESIGN BY:

:\ChampaignAp\030590302 Apron Rehab 2\Draw\ FILE: ELECTRICAL GATE DETAILS SHE UPDATE BY: Seon Smith PLOT DATE: 4/17/2008 7:57 PM

REVISIONS

BY

THIS BAR IS EQUAL TO 2" AT FULL SCALE (34X22).

PHASE

AIR CARRIER RAMP,

REHABILITATE

SHEET

S

DETAIL

GATE

ECTRIC

딥

DATE

NUMBER

DRAWN BY: CMT CHECKED BY: 8mb PROVED BY: 8mg DATE: 04/18/2008 JOB No: 0305903

CMI~3663 3-17-0015-XX SHEET 46 OF 57 SHEETS



Moving Gate Can Cause Injury or Death

KEEP CLEAR! Gate may move at any time without prior warning. Do not let children operate the gate or play in the gate area.

This entrance is for vehicles only Pedestrians must use separate entrance

WARNING SIGN DETAIL