

PIPE CULVERTS, CLASS C, TYPE 1 12" (TEMPORARY)		
STATION	LT/RT	QUANTITY FOOT
PRE-STAGE		
3986+39	RT	4
3988+08	RT	5
3989+31	RT	7
3990+91	RT	9
3991+48	RT	6
3994+10	RT	4
3995+63	RT	7
3998+60	RT	8
4004+23	RT	8
4004+49	RT	22
4006+81	RT	22
4013+10	LT	5
4019+80	LT	4
4031+51	LT	20
4032+41	LT	22
4033+69	LT	29
4034+85	LT	24
4035+04	LT	23
4035+78	LT	31
4038+56	LT	39
4038+78	LT	9
4039+44	LT	9
4039+54	LT	22
4040+28	LT	17
PRE-STAGE SUBTOTAL		356
STAGE 1		
3982+87	LT	54
4008+28	LT	34
4010+50	LT	13
4010+50	RT	8
4016+50	LT	21
4020+70	LT	12
4023+20	LT	22
4025+60	LT	15
4028+81	LT	11
4038+28	RT	24
4039+82	RT	37
4042+96	RT	10
4044+56	RT	9
4044+61	RT	4
STAGE 1 SUBTOTAL		274
STAGE 2		
4038+34	LT	13
4042+96	LT	9
4044+56	LT	8
STAGE 2 SUBTOTAL		30
PROJECT TOTAL		660

PERIMETER EROSION BARRIER			
FROM	TO	LT/RT	QUANTITY FOOT
PRE-STAGE			
3985+01	3990+50	RT	551
3997+29	4001+89	RT	537
4002+69	4008+34	RT	680
4007+93	4010+00	LT	207
4010+00	4013+65	LT	449
497+92	498+33	LT	42
4014+50	4020+96	LT	753
4021+63	4023+00	LT	138
4023+00	4030+77	LT	788
607+34	613+65	LT	664
602+00	607+00	LT	537
602+00	4045+00	LT	293
PRE-STAGE SUB-TOTAL			5639
STAGE 1			
3982+08	3984+41	LT	271
3984+80	3987+79	LT	397
3988+23	3993+18	LT	536
3994+30	3996+50	LT	221
3996+50	4001+77	LT	542
4008+91	4010+00	RT	129
4010+00	4013+51	RT	387
4014+61	416+36	RT	217
4016+78	4017+22	RT	57
4023+97	4030+90	RT	860
4031+72	4035+38	RT	434
4035+70	4036+50	RT	109
4036+50	602+00	RT	533
STAGE 1 SUB-TOTAL			4693
STAGE 3			
3994+50	3996+07	RT	277
583+62	586+58	RT	330
587+24	590+41	RT	333
590+60	593+78	RT	345
596+79	597+69	RT	138
585+00	591+65	LT	733
592+74	595+00	LT	275
595+00	596+03	LT	141
596+53	599+47	LT	426
STAGE 3 SUB-TOTAL			2998
PROJECT TOTAL			13330

INLET AND PIPE PROTECTION			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
3985+26	66	LT	1
PROJECT TOTAL			1

TEMPORARY DITCH CHECKS			
STATION	OFFSET	LT/RT	QUANTITY FOOT
PRE-STAGE			
3982+46	47.9	LT	15
3985+63	68.2	LT	15
3986+12	70.0	LT	15
3986+48	71.1	LT	15
3987+04	73.3	LT	15
PROJECT TOTAL			75

TEMPORARY CATCH BASINS			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
3986+40	46.6	RT	1
3988+10	47.9	RT	1
3989+33	48.5	RT	1
3990+92	48.8	RT	1
3992+49	48.6	RT	1
3994+11	48.6	RT	1
3995+65	48.8	RT	1
3998+63	49.0	RT	1
4000+27	49.5	RT	1
4012+48	51.5	LT	1
4013+09	59.4	LT	1
4019+77	60.1	LT	1
4031+42	41.9	LT	1
4034+98	47.7	LT	1
PROJECT TOTAL			14

TEMPORARY INLETS			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
4006+88	56.0	RT	1
4038+78	46.2	LT	1
4039+48	45.2	LT	1
PRE-STAGE SUBTOTAL			3
STAGE 1			
4010+50	58.4	RT	1
4044+60	68.0	RT	1
STAGE 1 SUBTOTAL			2
PROJECT TOTAL			5

REMOVING INLETS TO MAINTAIN FLOW			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
3985+99	35	RT	1
3988+23	1	RT	1
3988+24	35	RT	1
3989+33	34	RT	1
3990+01	34	RT	1
3994+20	34	RT	1
3994+32	1	RT	1
3995+64	34	RT	1
3997+06	34	RT	1
4004+33	34	RT	1
4006+72	13	LT	1
4010+32	13	LT	1
4027+13	10	LT	1
4034+55	3	RT	1
4038+13	5	LT	1
PROJECT TOTAL			15

REMOVING MANHOLES TO MAINTAIN FLOW			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
3985+12	42	RT	1
3988+10	39	RT	1
3990+92	40	RT	1
3994+11	40	RT	1
3996+93	39	RT	1
4020+77	57	LT	1
PROJECT TOTAL			6

REMOVING CATCH BASINS TO MAINTAIN FLOW			
STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE			
3987+10	35	RT	1
3992+59	34	RT	1
4006+74	33	RT	1
4039+41	34	LT	1
PROJECT TOTAL			4

INLET FILTERS					
EX DRAIN STRUCT NO.	PR DRAIN STRUCT NO.	STATION	OFFSET	LT/RT	QUANTITY EACH
PRE-STAGE					
641	-	-	-	-	1
640	-	-	-	-	1
639	-	-	-	-	1
638	-	-	-	-	1
637	-	-	-	-	1
629	-	-	-	-	1
-	-	3986+40	47	RT	1
627	-	-	-	-	1
-	-	3988+10	48	RT	1
623	-	-	-	-	1
-	-	3989+33	49	RT	1
621	-	-	-	-	1
-	-	3990+92	49	RT	1
618	-	-	-	-	1
-	-	3992+49	49	RT	1
616	-	-	-	-	1
617A	-	-	-	-	1
-	-	3994+11	49	RT	1
612	-	-	-	-	1
614A	-	-	-	-	1
-	-	3995+65	49	RT	1
610	-	-	-	-	1
607	-	-	-	-	1
-	-	3998+63	41	RT	1
604	-	-	-	-	1
600	-	-	-	-	1
-	-	4000+27	50	RT	1
711	-	-	-	-	1
-	-	4002+10	139	RT	1
710	-	-	-	-	1
-	-	4002+43	136	RT	1
721	-	-	-	-	1
724	-	-	-	-	1
-	811	-	-	-	1
726	-	-	-	-	1
729	-	-	-	-	1
730	-	-	-	-	1
-	-	4006+88	56	RT	1
731	-	-	-	-	1
732	-	-	-	-	1
791	-	-	-	-	1
790	-	-	-	-	1
733	-	-	-	-	1
734	-	-	-	-	1
742	-	-	-	-	1
744	-	-	-	-	1
739	-	-	-	-	1
-	-	4011+47	52	LT	1
737	-	-	-	-	1
-	-	4013+09	60	LT	1

DESIGNED	PJO	REVISED	-
DRAWN	KES	REVISED	-
CHECKED	JCM	REVISED	-
DATE	12/14/2012	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
EROSION CONTROL ITEMS

SCALE: SHEET NO. 11 OF 13 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
338	(112 & 113) WRS-6	DUPAGE	734	60
CONTRACT NO. 60R31				
ILLINOIS FED. AID PROJECT				