

PIPE NUM.	STORM SEW 8 FOOT	STORM SEW 10 FOOT	STORM SEW 12 FOOT	STORM SEW 15 FOOT	STORM SEW 18 FOOT	STORM SEW 21 FOOT	STORM SEW 24 FOOT	STORM SEW 27 FOOT	STORM SEW 30 FOOT	STORM SEW 36 FOOT	STORM SEW 42 FOOT	9' X 5' BC FOOT	COMMENTS
791			25										
810												89.2	PAID FOR AS REM EXIST STRUCT NI
820									***				
821													72" TO REMAIN 130.3
822											68.7*		
823											83.7*		
824											***		
830			21.1										
831							212.2						
832			24.2										
833			46.9										
834			51.6										
835			48.4										
836			37										
837							211.2						
838			26.4										
839			45.4										
840			35.7										
841			35.5										
842								585.9					
842A	13.5												
842B	12												
843			77.7										
844			44.9										
845			6.8										
846			39.6										
847			84.5										
848			13										
849			4.6										
850			19.5										
851			42.2										
852								318					
853			6.5										
854			48.1										
855			6.9										
856			48										
857			5.5										
858			42.2										
859			6										
860			9.7										
122					3.2*								
123								37.2*					
124								***					
130			54.6										
131			182.5										68.5' TO REMAIN
132			***										
151			74.3										
151A	66.4												
152			79.3										
153			203.9*										
160			1										
161			2										
162			31.6										
163			5.3*										
164			2*										
165			36.5*										
166			64.8*										
167			45.8										
168			38.3*										
TOTAL	92	259	4766	15	1279		1812	1086	1963	1128			

PIPE NUM.	STORM SEW 8 FOOT	STORM SEW 10 FOOT	STORM SEW 12 FOOT	STORM SEW 15 FOOT	STORM SEW 18 FOOT	STORM SEW 21 FOOT	STORM SEW 24 FOOT	STORM SEW 27 FOOT	STORM SEW 30 FOOT	STORM SEW 36 FOOT	STORM SEW 42 FOOT	9' X 5' BC FOOT	COMMENTS
171			36.9*										
171A		8.9											
172			7.6*										
173				142.2*									
180	30.7*												
181			55.4*										
200			77.3										
201			6.7										
202			568.5										
203			86.2										
204			28.2										
205					43.1								
206					305.7								
207					51.1								
208					109.7*								
212							39.5*						
213							28.9*						
TOTAL	92	259	4766	15	1279		1812	1086	1963	1128			

123.4 - PIPE LENGTH TO BE REMOVED  
123.4\* - PIPE LENGTH TO REMAIN  
\*\*\* - UNKNOWN PIPE LENGTH

DESIGNED *PJD*  
DRAWN *KES*  
CHECKED *JCM*  
DATE *12/17/2012*

REVISED - ADDENDUM A 02/22/2013  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EXISTING DRAINAGE PIPE SCHEDULE OF QUANTITIES

SCALE: AS SHOWN SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE. 338 SECTION (112 & 113) WRS-6 COUNTY DUPAGE TOTAL SHEETS 734 SHEET NO. 274 CONTRACT NO. 60R31 ILLINOIS FED. AID PROJECT