PIPE NUM	STORM SEWERS, CLASS A, TYPE 1 12" FT	STORM SEWERS, CLASS A, TYPE 2 12" FT	STORM SEWERS, CLASS A, TYPE 3 12" FT	STORM SEWERS, CLASS A, TYPE 1 15" FT	STORM SEWERS, CLASS A, TYPE 2 15" FT	STORM SEWERS, CLASS A, TYPE 1 18" FT	STORM SEWERS, CLASS A, TYPE 2 18" FT	STORM SEWERS, CLASS A, TYPE 3 18" FT	STORM SEWERS, CLASS A, TYPE 1 24" FT	STORM SEWERS, CLASS A, TYPE 2 24" FT	STORM SEWERS, CLASS A, TYPE 3 24" FT	STORM SEWERS, CLASS A, TYPE 1 30" FT	STORM SEWERS, CLASS A, TYPE 2 30" FT	STORM SEWERS, CLASS A, TYPE 1 36" FT	STORM SEWERS, CLASS A, TYPE 2 36" FT	STORM SEWERS, CLASS A, TYPE 1 48" FT	STORM SEWERS, CLASS A, TYPE 2 60" FT	STORM SEWERS, RG CLASS A, TYPE 1 12" FT	STORM SEWERS, RG CLASS A, TYPE 2 12" FT	STORM SEWERS, RG CLASS A, TYPE 1 15" FT	STORM SEWERS, RG CLASS A, TYPE 2 15" FT	STORM SEWERS, RG CLASS A, TYPE 2 18" FT	STORM SEWERS, RG CLASS A, TYPE 1 24" FT	STORM SEWERS, RG CLASS A, TYPE 2 24" FT	STORM SEWERS, RG CLASS A, TYPE 1 30" FT	STORM SEWERS, RG CLASS A, TYPE 2 36" FT	STORM SEWERS, RG CLASS A, TYPE 2 60" FT	STORM SEWERS DUCTILE IRON, 12" FT	STORM SEWERS DUCTILE IRON, 14" FT	STORM SEWERS DUCTILE IRON, 18" FT		PIPE SLOPE (%)	TRENCH BACKFILL CU YD	COMMENTS
48	87.4																															0.50%	16	
49	2.0																															0.50%	1	
50							86.0																									0.50%	27	
51	81.7																															0.50%	13	
51A	11.4																															0.50%	2	
52		1.5																														0.50%	1	
53																								96.4								0.18%	32	
54																			72.9													0.50%	13	
55		3.0																														0.50%	1	
56										95.5																						0.18%	66	
57																		74.5														0.50%	12	
57A	17.6																															0.50%	3	
58		3.9																														0.50%	1	
59												95.0																				0.13%	35	
60																		71.4														0.50%	11	
61	6.3																															0.50%	1	
62												60.1																				0.13%	10	
63																		67.3														0.50%	11	
64																			4.2													0.50%	1	
65												71.9																				0.13%	14	
66																		91.0														0.50%	13	
67																		62.0														0.50%	9	
71																		34.0														1.00%	6	
72																			15.0													1.00%	4	
80A		111.5																														1.00%	107	
80B																			25.8													1.00%	23	
80		40.5																														1.00%	33	
81																			22.0													1.00%	19	
81A		256.0																														0.50%	99	
82	35.3																															1.00%	7	
83																				14.0												0.50%	3	
400																							12.8									0.31%	5	
401								227.0																								0.26%	94	
402								896.0																								0.27%	164	
404								294.4																								0.27%	96	
407A						141.1																										0.18%	44	
407B						141.1																										0.18%	44	
407C						141.1																										0.18%	44	
TOTAL	1,134	5,168	41	127	857	426	586	98	918	1,399	8	227	946	21	1,173	238	1,114	1,258	2,119	14	254	152	13	192	145	156	195	107	36	92				12,972	

		DESIGNED PJO	REVISED - ADDENDUM A 02/22/2013	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PROPOSED DRAINAGE PIPE SCHEDULE OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN KES	REVISED -			338	1112 & 1131 WRS-6	DUPAGE	734	288
		CHECKED JCM	REVISED -		SCALE: AS SHOWN | SHEET NO. 7 OF 7 SHEETS | STA. TO STA.		SC-20	CONTRACT NO. 60R31		
		DATE 12/14/2012	REVISED -				ILLINOIS FED. AID PROJECT			