

FILE NAME: G:\Projects\ILLINOIS Department of Transportation\162 - Item 7 - Various Vertical Work Order No. B - IL 58 Plans\Cadd Sheets\0162175-sh-501.dgn

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0021	90% FEDERAL	10% STATE	SAFETY
20200100	EARTH EXCAVATION	CU YD	910	910			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	115	115			
20800150	TRENCH BACKFILL	CU YD	65	65			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SO YD	1,307	1,307			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	47	47			
25000210	SEEDING, CLASS 2A	ACRE	0.2	0.2			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18			
28000305	TEMPORARY DITCH CHECKS	FOOT	190	190			
28000400	PERIMETER EROSION BARRIER	FOOT	2,736	2,736			
28000500	INLET AND PIPE PROTECTION	EACH	22	22			
28001100	TEMPORARY EROSION CONTROL BLANKET	SO YD	1,139	1,139			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	1,324	1,324			
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	1,257	1,257			

URBAN

15

SHT. PLAN	USER NAME: mmiller	DESIGNED - BFH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE: 100.0000' = 1" (1/4")	DRAWN - BFH	REVISED -				338	013R-2IN	WILL	38	3
	PLOT DATE: 3/21/2013	CHECKED - BA	REVISED -		SCALE: N.T.S.	SHEET 1 OF 4 SHEETS	STA. TO STA.	CONTRACT NO. 60T95			
		DATE - 3/19/13	REVISED -		ILLINOIS FED. AID PROJECT						