

EARTHWORK SCHEDULE

STATION	STATION	EARTH EXCAVATION (20200100)	TOPSOIL/ UNSUITABLE	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE (+/-) (+) = WASTE (-) = SHORTAGE	TOPSOIL EXCAVATION AND PLACEMENT (21101505)
		CU YD	CU YD	CU YD	CU YD	CU YD	CU YD
494+25.00	495+00.00	19	9	16	2	14	6
495+00.00	496+00.00	73	19	62	4	58	10
496+00.00	497+00.00	93	19	79	2	77	8
497+00.00	498+00.00	106	15	90	0	90	2
498+00.00	499+00.00	119	15	101	0	101	0
499+00.00	500+00.00	58	8	49	0	49	0
500+00.00	501+00.00	62	8	53	0	53	0
501+00.00	502+00.00	117	15	99	0	99	0
502+00.00	503+00.00	110	15	94	0	94	0
503+00.00	504+00.00	86	15	73	0	73	4
504+00.00	505+00.00	52	15	44	0	44	10
505+00.00	505+73.00	15	9	13	0	13	7
505+73.00	506+00.00	0	0	0	0	0	0
IL RT 59 TOTAL		910	162	773	8	765	47

NOTE: 15% SHRINKAGE FACTOR

EARTHWORK SUMMARY TABLE

DESCRIPTION	QUANTITY	UNIT
EARTH EXCAVATION	910	CU YD
EXTRA EXCAVATION	765	CU YD
TOPSOIL / UNSUITABLE EXCAVATION:		
TOTAL TOPSOIL EXCAVATION -	162	CU YD
EXCAVATED TOPSOIL TO BE USED AS:		
TOPSOIL EXCAVATION AND PLACEMENT -	47	CU YD
EXCESS EXCAVATED TOPSOIL TO BE:		
REMOVED AND DISPOSED OF AS UNSUITABLE MATERIAL -	115	CU YD

FILE NAME : G:\Projects\ILLINOIS Department of Transportation\PTB 162 - Item 7 - Various Various Work Order No. 8 - IL 59 Plans\Cadd Sheets\0160TSP-sht-schedule.dgn

SHT.PLAN	USER NAME = mmiller	DESIGNED - BFH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 48.0000' / in.	DRAWN - BFH	REVISED -					338	(113R-2)N	WILL	38	9
	PLOT DATE = 3/21/2013	CHECKED - BA	REVISED -		SCALE: N.T.S.	SHEET 1	OF 1	SHEETS	STA.	TO STA.	CONTRACT NO. 60T95	
		DATE - 3/19/13	REVISED -								ILLINOIS FED. AID PROJECT	