

# SCHEDULE OF QUANTITIES

**48101200 AGGREGATE SHOULDERS, TYPE B**

**LOCATION #1 / F.A.P. RTE. 317 (U.S.24) / MCLEAN COUNTY**

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVE. DEPTH (INCH)	QUANTITY (TON)	
RT. SHOULDER	1159+98.00		1202+96.00	4298.00	4.00	1.375	131.33	
RT. SHOULDER	1202+96.00		1493+56.58	29060.58	4.00	1.375	887.96	
RT. SHOULDER	1494+43.42		1518+50.00	2406.58	4.00	1.375	73.53	
LT. SHOULDER	1133+00.00		1134+00.00	100.00	4.00	1.375	3.06	
LT. SHOULDER	1159+98.00		1202+96.00	4298.00	4.00	1.375	131.33	
LT. SHOULDER	1202+96.00		1493+56.58	29060.58	4.00	1.375	887.96	
LT. SHOULDER	1494+43.42		1518+50.00	2406.58	4.00	1.375	73.53	
TOTAL =							2188.70	TON
USE =							2189.00	TON

**NOTE:**

**FOR QUANTITIES AT LOCATION #2 SEE SHEET NUMBER 16**

**48101200 AGGREGATE SHOULDERS, TYPE B**

**LOCATION #3 / F.A.S. RTE. 1517 (U.S. 150) / MCLEAN COUNTY**

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVE. DEPTH (INCH)	QUANTITY (TON)	
RT. SHOULDER	1026+75.00		1147+82.00	12107.00	3.00	1.375	277.45	
LT. SHOULDER	1026+75.00		1147+82.00	12107.00	3.00	1.375	277.45	
TOTAL =							554.90	TON
USE =							555.00	TON

- SHOULDER REPAIR FY2013-1
- DEWITT, MCLEAN & PIATT

FILE NAME =	USER NAME = ceerlockjd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\ceerlockjd\0336878\0570A23-sht-Schedules.dgn	DRAWN -	REVISED -	VAR.					.	**	17	15	
*MODELNAME*	PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -		SCALE:			SHEET 1 OF 2 SHEETS STA. TO STA.			CONTRACT NO. 70A23	
	PLOT DATE = 3/20/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							