

SCHEDULE OF QUANTITIES

48101200 AGGREGATE SHOULDERS, TYPE B
LOCATION #1 / F.A.P. RTE. 749 (IL. 133)
EDGAR COUNTY

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVE. DEPTH (INCH)	QUANTITY (TON)
RT. SHOULDER	991+50.00		1059+12.07	6762.07	4.00	1.375	206.62
RT. SHOULDER	1059+12.07		1080+50.00 (BK)	2137.93	4.00	1.375	65.33
RT. SHOULDER	7+79.47 (AH)		158+35.80	15056.33	4.00	1.375	460.05
RT. SHOULDER	161+82.20		190+64.20	2882.00	4.00	1.375	88.06
RT. SHOULDER	190+64.20		244+00.00	5335.80	4.00	1.375	163.04
RT. SHOULDER	244+00.00		247+00.00	300.00	4.00	1.375	9.17
RT. SHOULDER	247+00.00		312+20.70 (BK)	6520.70	4.00	1.375	199.24
RT. SHOULDER	309+71.20 (AH)		417+80.00	10808.80	4.00	1.375	330.27
RT. SHOULDER	418+50.00		581+27.40 (BK)	16277.40	4.00	1.375	497.37
RT. SHOULDER	602+51.50 (AH)		623+25.00	2073.50	4.00	1.375	63.36
RT. SHOULDER	623+25.00		694+92.30	7167.30	4.00	1.375	219.00
LT. SHOULDER	991+50.00		1059+12.07	6762.07	4.00	1.375	206.62
LT. SHOULDER	1059+12.07		1080+50.00 (BK)	2137.93	4.00	1.375	65.33
LT. SHOULDER	7+79.47 (AH)		158+35.80	15056.33	4.00	1.375	460.05
LT. SHOULDER	161+82.20		190+64.20	2882.00	4.00	1.375	88.06
LT. SHOULDER	190+64.20		244+00.00	5335.80	4.00	1.375	163.04
LT. SHOULDER	244+00.00		247+00.00	300.00	4.00	1.375	9.17
LT. SHOULDER	247+00.00		312+20.70 (BK)	6520.70	4.00	1.375	199.24
LT. SHOULDER	309+71.20 (AH)		417+80.00	10808.80	4.00	1.375	330.27
LT. SHOULDER	418+50.00		581+27.40 (BK)	16277.40	4.00	1.375	497.37
LT. SHOULDER	602+51.50 (AH)		623+25.00	2073.50	4.00	1.375	63.36
LT. SHOULDER	623+25.00		694+92.30	7167.30	4.00	1.375	219.00
TOTAL =							4603.00 TON
USE =							4603.00 TON
RURAL =							4165.00 TON
URBAN =							438.00 TON

48101200 AGGREGATE SHOULDERS, TYPE B
LOCATION #2 / F.A.P. RTE. 836 (IL. 49)
DOUGLAS & EDGAR COUNTY

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVE. DEPTH (INCH)	QUANTITY (TON)
RT. SHOULDER	0+00.00		4+30.00	430.00	4.00	1.375	13.14
RT. SHOULDER	4+30.00		9+67.10	537.10	2.00	1.375	8.21
RT. SHOULDER	9+67.10		14+52.30	485.20	4.00	1.375	14.83
RT. SHOULDER	14+52.30		22+20.20	767.90	4.00	1.375	23.46
RT. SHOULDER	22+20.20		25+63.00	342.80	4.00	1.375	10.47
RT. SHOULDER	26+63.00		52+17.28	2554.28	4.00	1.375	78.05
RT. SHOULDER	53+33.11		69+65.10	1631.99	4.00	1.375	49.87
RT. SHOULDER	70+08.90		124+86.86 (BK)	5477.96	4.00	1.375	167.38
RT. SHOULDER	125+00.00 (AH)		135+02.17	1002.17	4.00	1.375	30.62
RT. SHOULDER	135+78.83		321+00.00	18521.17	4.00	1.375	565.92
LT. SHOULDER	0+00.00		4+30.00	430.00	4.00	1.375	13.14
LT. SHOULDER	4+30.00		9+67.10	537.10	4.00	1.375	16.41
LT. SHOULDER	9+67.10		14+52.30	485.20	4.00	1.375	14.83
LT. SHOULDER	14+52.30		22+20.20	767.90	3.00	1.375	17.60
LT. SHOULDER	22+20.20		25+63.00	342.80	4.00	1.375	10.47
LT. SHOULDER	26+63.00		52+17.28	2554.28	4.00	1.375	78.05
LT. SHOULDER	53+33.11		69+65.10	1631.99	4.00	1.375	49.87
LT. SHOULDER	70+08.90		124+86.86 (BK)	5477.96	4.00	1.375	167.38
LT. SHOULDER	125+00.00 (AH)		135+02.17	1002.17	4.00	1.375	30.62
LT. SHOULDER	135+78.83		321+00.00	18521.17	4.00	1.375	565.92
TOTAL =							1926.24 TON
USE =							1927.00 TON
DOUGLAS COUNTY =							122.00 TON
EDGAR COUNTY =							1805.00 TON

48101200 AGGREGATE SHOULDERS, TYPE B
LOCATION #3 / F.A.P. RTE. 824 (U.S. 45)
DOUGLAS COUNTY

LOCATION	STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AVE. DEPTH (INCH)	QUANTITY (TON)
RT. SHOULDER	617+97.00		724+32.05	10635.05	4.00	1.375	324.96
LT. SHOULDER	617+97.00		724+32.05	10635.05	4.00	1.375	324.96
TOTAL =							649.92 TON
USE =							650.00 TON

•SHOULDER REPAIR FY2013-2
 ** DOUGLAS & EDGAR