

LOCATION #1

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES, & LOCATION DESCRIPTIONS
3	SUMMARY OF QUANTITIES
4-9D	EXISTING STRUCTURE PLANS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED AFTER SHEET NO. 9:

STANDARDS	DESCRIPTION
STANDARD 701101-03	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701106-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701400-06	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701402-09	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701606-08	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES
STANDARD 701901-02	TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" ADOPTED JANUARY 1, 2012; THE SUPPLEMENTAL SPECIFICATIONS, THE RECURRING SPECIAL PROVISIONS, AND THE SPECIAL PROVISIONS INCLUDED IN THE PROPOSAL.

THE PROPOSED PROJECT IS LOCATED AT 2 LOCATIONS IN MACON COUNTY IN DISTRICT 7, THE LOCATIONS ARE AT STRUCTURE NUMBERS 058-0103 AND 058-0112 IN MACON COUNTY.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF CLEANING AND PAINTING THE BRIDGES AS SPECIFIED IN THE PLANS AND SPECIAL PROVISIONS.

THE STRUCTURAL STEEL SHALL BE CLEANED AND PAINTED AS SPECIFIED IN THE PLANS AND THE SPECIAL PROVISIONS.

ALL DECK DRAINS ON STRUCTURE NUMBER 058-0103 SHALL BE PAINTED ACCORDING TO THE REQUIREMENTS OF PAINT SYSTEM 1 - OZ/E/U. ANY DAMAGE CAUSED BY THE CONTRACTOR SHALL BE REPAIRED AT THEIR OWN EXPENSE AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

ONLY STRUCTURAL STEEL IS TO BE PAINTED. ALL OTHER SURFACES WILL BE PROTECTED FROM BEING PAINTED. ALL PAINT AND OVERSPRAY WILL BE REMOVED AT THE CONTRACTOR'S EXPENSE.

THE SSPC OPI AND OP2 PAINTING CONTRACTOR CERTIFICATION WILL BE REQUIRED FOR THIS PROJECT.

ROUTE: FAP 322
 MARKED: US 51
 SECTION: 58-20HB-2
 STATION: 312+43.08
 STRUCTURE NUMBER: 058-0103

TYPE OF BRIDGE: Wide Flange I Beams-4 Spans (6 Beams)
 LOCATION: 1 Mile southwest of Decatur
 FEATURE CARRIED/SPANNED: CH 41 over US 51

COLOR OF THE FINISH COAT SHALL BE GRAY, MUNSELL 5B 7/1.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All beams, bearing and other structural steel within 10 of the beam ends at the south abutment, all structural steel in span 4, and the remaining fascias girders, and their bearings, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

Three air monitors will be required at this location.

LOCATION #2

ROUTE: FAP 714
 MARKED: ILL 105
 SECTION: 128 8Y
 STATION: 116+30
 STRUCTURE NUMBER: 058-0112

TYPE OF BRIDGES: Wide Flange I Beams-3 Spans (10 Beams)
 LOCATION: 0.3 miles east of IL 48 on south side of Decatur
 FEATURE CARRIED/SPANNED: ILL 105 over Spring Creek

COLOR OF THE FINISH COAT SHALL BE GREEN, MUNSELL 10B 3/6.

Cleaning and painting of the existing structural steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All six weathering steel beams, including bearings and diaphragms, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning. For the outer four beams, all structural steel, including bearings and diaphragms, within 5' (measured along the beam) of the abutments, shall be cleaned by SSPC-SP10- Near White Metal Blast Cleaning.

The designated areas cleaned per Near White Metal Blast Cleaning - SSPC-SP10 shall be painted according to the requirements of Paint System 1 - OZ/E/U.

Four air monitors will be required at this location.

FILE NAME -	USER NAME - steffennk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, GENERAL NOTES AND STRUCTURE LOCATION DESCRIPTIONS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\p\dot\steffennk\033033\03	4613-shc-index.dgn	DRAWN -	REVISED -			322		MACON	9	2
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -							CONTRACT NO. 74613
	PLOT DATE = 4/29/2013	DATE -	REVISED -			SCALE: N/A	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT

• DT BRIDGE PAINTING 2013-4