CURB & GUTTER REMOVAL SCHEDULE

LOCATION	SIDE	GUTTER REMOVAL (FT)	CURB REMOVAL (FT)	CC&G REMOVAL (FT)
IL RTE 159				
167+65 TO 168+56	RT			82
167+65 TO 168+69	LT			109
168+69 TO 169+00	RT			35
168+84 TO 168+99	LT			19
169+23 TO 170+09	LT			86
169+24 TO 169+31	RT			11
169+39 TO 169+78	RT			47
169+86 TO 170+49	RT			66
170+15 TO 170+21	LT			9
170+61 TO 171+97	LT			143
170+62 TO 171+25	RT			70
170+74 TO 170+98	LT		49	
171+37 TO 171+84	RT			53
171+95 TO 172+89	RT			100
172+14 TO 175+82	LT			380
173+10 TO 174+46	RT			141
174+70 TO 175+38	RT			72
175+52 TO 176+58	RT			108
176+46 TO 176+85	LT			44
176+77 TO 176+78	RT			3
177+29 TO 177+66	RT			36
177+46 TO 177+99	RT			53
177+79 TO 178+16	LT			44
178+21 TO 179+58	RT			135
178+54 TO 178+82	LT			31
178+73 TO 178+76	LT			51
179+08 TO 179+18	LT			12
179+18 TO 179+28	LT			70
179+24 TO 179+32	LT			39
179+34 TO 179+38	LT			23
179+35 TO 180+55	LT			121
179+39 TO 179+44	LT			19
179+93 TO 180+38	RT			47
180+57 TO 180+74	RT			17
180+59 TO 180+57	LT			24
180+80 TO 180+79	LT			57
180+88 TO 182+60	RT			173
181+15 TO 183+28	LT			214
182+63 TO 182+67	RT			7
183+04 TO 183+43	RT			40
183+31 TO 183+34	LT			33
183+45 TO 183+58	LT			34
183+63 TO 184+41	RT			79
183+69 TO 183+84	LT			64
184+05 TO 184+10	LT			29
184+23 TO 184+44	LT			67
184+26 TO 184+44	LT			19
184+65 TO 185+04	RT			43
184+67 TO 185+41	LT			74
184+68 TO 184+91	LT			70
184+68 TO 185+05	RT			40
184+68 TO 186+00	LT			135
185+39 TO 185+77	RT			43
185+40 TO 185+77	RT			54
186+11 TO 186+61	RT			111
186+37 TO 186+89	LT			55
186+74 TO 187+71	LT		130	
186+94 TO 188+66	RT			177
187+00 TO 187+69	LT			70
187+96 TO 188+93	LT		97	
187+99 TO 188+92	LT			93
189+20 TO 190+09	LT		94	
189+22 TO 190+07	RT			94
189+27 TO 189+60	RT			38
190+37 TO 190+55	LT		22	
190+62 TO 190+87	RT			31
190+73 TO 190+90	LT		24	
191+26 TO 191+58	LT			40
191+34 TO 193+12	RT			185
192+01 TO 192+25	LT			38
192+72 TO 193+30	LT			63
193+40 TO 196+72	RT			339
193+63 TO 194+12	LT			58
194+27 TO 194+88	LT			73
194+97	LT			18
194+98 TO 195+03	LT			16
195+42 TO 195+77	LT			44
196+16 TO 196+68	LT			59
196+78 TO 196+87	LT			17
196+83 TO 197+43	RT			63
197+01 TO 197+25	LT			24
SUBTOTAL (1)		0	416	5281

CURB & GUTTER REMOVAL SCHEDULE (CONT'D)

LOCATION	SIDE	GUTTER REMOVAL (FT)	CURB REMOVAL (FT)	CC&G REMOVAL (FT)
197+41 TO 198+12	LT			71
197+60 TO 198+02	RT			42
198+02 TO 198+11	RT			21
198+41 TO 199+32	LT			92
198+42 TO 198+45	RT			14
198+62 TO 199+79	RT			117
199+74 TO 200+32	LT			64
200+12 TO 200+50	RT			37
200+46 TO 200+68	LT			28
200+75 TO 201+58	LT			86
200+57 TO 200+81	RT			42
200+96 TO 201+21	RT			26
201+79 TO 202+87	LT			109
201+95 TO 203+63	RT			168
203+06 TO 203+59	LT			54
203+97 TO 204+70	RT			73
204+01 TO 205+50	LT			152
204+96 TO 207+18	RT			254
205+68 TO 207+16	LT			154
207+58 TO 210+07	RT			283
207+62 TO 209+84	LT			234
210+25 TO 214+74	LT			450
210+61 TO 212+65	RT			207
213+14 TO 214+06	RT			93
214+17 TO 214+52	LT		54	
214+26 TO 214+74	RT			49
215+04 TO 216+21	LT			122
215+21 TO 215+67	RT			48
215+85 TO 217+35	RT			151
216+44 TO 216+80	LT			36
217+00 TO 217+85	LT			85
217+39 TO 217+47	RT			47
217+82 TO 217+81	RT			44
217+85 TO 218+43	RT			59
218+40 TO 218+80	LT			41
218+82 TO 219+85	RT			105
219+77 TO 219+89	LT			22
220+02 TO 221+33	RT			131
220+19 TO 220+86	LT			80
221+00 TO 221+21	LT			23
221+42 TO 222+14	LT			72
222+36 TO 222+87	LT			52
222+69 TO 223+51	RT			92
222+71 TO 222+79	RT			16
223+04 TO 223+71	LT			89
223+81 TO 223+93	RT			31
223+81 TO 223+94	RT			13
223+98 TO 224+77	LT			106
224+14 TO 224+43	RT			40
224+16 TO 224+42	RT			36
224+78	LT			19
224+79 TO 225+89	RT			123
224+81 TO 225+85	RT			106
225+07	LT			14
225+07 TO 226+86	LT			192
226+33 TO 227+87	RT			199
226+36 TO 228+06	RT			172
226+86	LT			24
227+16 TO 227+65	LT			52
228+05 TO 228+43	LT			41
228+16 TO 228+40	LT			25
228+50 TO 231+83	RT			337
228+75 TO 229+13	LT			47
228+76 TO 228+82	LT			7
229+36 TO 229+61	LT			34
229+91 TO 230+77	LT			95
230+97 TO 232+95	LT			203
232+20 TO 236+38	RT			440
233+12 TO 234+10	LT			101
234+36 TO 236+48	LT			219
236+26 TO 236+33	RT			16
236+69 TO 237+50	RT			90
E MADISON AVE				
0+41 TO 1+32	LT			97
0+41 TO 1+92	RT			162
1+42 TO 2+07	LT			72
2+02 TO 2+07	RT			17
SUBTOTAL (2)		0	54	7365

CURB & GUTTER REMOVAL SCHEDULE (CONT'D)

LOCATION	SIDE	GUTTER REMOVAL (FT)	CURB REMOVAL (FT)	CC&G REMOVAL (FT)
WICKLIFFE AVE				
58+00 TO 58+12	RT		12	
58+00 TO 58+86	LT			90
58+43 TO 58+74	RT			38
58+83 TO 58+93	LT			162
58+95 TO 59+30	RT			44
59+08 TO 59+65	LT			210
59+09 TO 59+20	LT			65
60+24 TO 60+37	LT			16
60+26 TO 61+01	RT			75
60+73 TO 60+93	LT			27
61+20 TO 61+36	RT			17
61+47 TO 61+54	LT			13
61+62 TO 61+68	RT			13
61+78 TO 62+00	LT			22
61+81 TO 61+90	RT			12
61+87 TO 62+00	RT			13
VALLEY LN				
1+10 TO 1+24	LT		33	
E PARK AVE				
66+00 TO 69+72	LT	372		
66+00 TO 69+72	RT	373		
67+01 TO 67+17	LT			88
67+80 TO 69+34	LT			180
67+69 TO 68+00	LT			48
SPRING ST				
80+80 TO 80+87	RT			11
BROWN AVE				
0+32 TO 0+85	RT			54
0+41 TO 0+58	LT			30
0+62 TO 0+69	RT			12
0+79 TO 0+90	LT			17
WADSWORTH ST				
0+34 TO 0+70	RT			36
0+30 TO 0+70	LT			42
REBECCA AVE				
0+31 TO 1+10	RT			79
ALLEY @ 201+69				
0+24 TO 1+02	LT			79
0+23 TO 1+00	RT			78
TILLOTSON AVE				
3+30 TO 4+33	LT	103		
3+28 TO 4+33	RT	105		
ALLEY @ 205+61				
0+32 TO 1+05	LT			82
0+04 TO 1+05	RT			74
HIGH SCHOOL AVE				
0+33 TO 1+15	RT			82
UNION AVE				
0+20 TO 1+60	RT	142		
0+26 TO 1+60	LT	137		
WILSON AVE				
100+34 TO 100+88	RT			76
100+37 TO 100+88	LT			56
INDIANA AVE				
0+00 TO 0+54	RT	62		
0+28 TO 0+54	LT	71		
0+37 TO 0+49	LT			16
0+56 TO 1+80	LT	126		
0+57 TO 1+80	RT	125		
ALLEY @ 223+94				
0+31 TO 0+75	LT			43
ILLINOIS AVE				
1+02 TO 1+45	LT			105
SUBTOTAL (3)		1616	45	2105

CURB & GUTTER REMOVAL SCHEDULE (CONT'D)

LOCATION	SIDE	GUTTER REMOVAL (FT)	CURB REMOVAL (FT)	CC&G REMOVAL (FT)
CALIFORNIA AVE				
0+19 TO 1+10	RT			90
0+43 TO 1+10	LT			71
CLAREMONT CT				
0+34 TO 0+67	RT			35
0+42 TO 0+68	LT			26
SUBTOTAL (4)		0	0	222
SUBTOTAL (1)		0	416	5281
SUBTOTAL (2)		0	54	7365
SUBTOTAL (3)		1616	45	2105
SUBTOTAL (4)		0	0	222
TOTALS		1616	515	14973

STRIP REFLECTIVE CRACK CONTROL TREATMENT SCHEDULE

LOCATION	SIDE	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FT)
IL RTE 159		
227+25 TO 231+09	RT	383.4
232+20 TO 235+85	RT	364.8
EXISTING RUMBLE MEDIAN - STA 227+25 TO 237+50	LT/RT	2050.0
TOTAL		2798.2

MEDIAN SCHEDULE

LOCATION	SIDE	CONCRETE MEDIAN SURFACE 4" (SQ FT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06 (FT)	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (FT)	CONCRETE MEDIAN, TYPE SM-4.06 (SQ FT)	PCC SIDEWALK, 4" (SQ FT)
IL RTE 159						
164+25	LT				95.8	
166+99	LT	252.3	51.3	27.8		59.9
167+00	RT	146.6	43.9	24.6		95.4
170+41	LT	248.5	51.3	27.8		62.6
187+07	RT	439.8	34.8	78.0		194.4
TOTAL		1087.2	181.3	158.2	95.8	412.3