

PAVEMENT SCHEDULE														
LOCATION	POLYMERIZED HMA SURFACE COURSE, MIX E, N90 (TON)			HMA BINDER COURSE, IL-19.0, N90 (TON)				AGGREGATE BASE COURSE, TYPE A (SQ YD)		PCC BASE COURSE, 11.5" (SQ YD)	HMA SURFACE REMOVAL, VARIABLE DEPTH (SQ YD)	HMA SURFACE REMOVAL, 1.5" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (TON)	AGGREGATE (PRIME COAT) (TON)
	1.5"	2.0"	2.5"	2.25"	4.0"	6.25"	11.5"	8"	12"					
IL RTE 159														
163+05.00 to 167+65.00	244.6										2912.0	0.91	5.8	
167+65.00 TO 169+50.00			126.6					582.5	1019.2			0.28	1.8	
169+50.00 TO 174+50.00			367.3					1689.4	2922.4			0.82	5.2	
174+50.00 TO 179+50.00			427.8					1967.8	3298.9			0.96	6.1	
179+50.00 TO 184+00.00			385.0					1771.0	3023.3			0.86	5.5	
184+00.00 TO 189+50.00			470.9					2166.0	3563.3			1.05	6.7	
189+50.00 TO 195+00.00			470.5					2164.1	3601.7			1.05	6.7	
195+00.00 TO 200+50.00			470.8					2165.9	3625.3			1.05	6.7	
200+50.00 TO 206+00.00			470.6					2164.6	3631.1			1.05	6.7	
206+00.00 TO 212+00.00			513.3					2361.3	3999.0			1.15	7.3	
212+00.00 TO 218+00.00			513.3					2361.3	4042.1			1.15	7.3	
218+00.00 TO 223+50.00			473.8					2179.6	3686.1			1.06	6.8	
223+50.00 TO 229+50.00			513.4					1574.8	2657.3		1043.6	1.15	7.3	
229+50.00 TO 235+00.00			470.7					2.7	74.1	69.9	2002.6	1.05	6.7	
235+00.00 TO 237+50.00			218.4						14.3	14.3	1294.5	0.49	3.1	
ALLEY 168+75		16.1					32.2					0.05	0.3	
E MADISON AVE		67.6		76.0				144.5				0.19	1.2	
E WICKLIFFE AVE	143.7					598.8		280.9				0.54	3.4	
VALLEY AVE		32.5		36.6				67.6				0.09	0.6	
VALLEY LN		23.8		26.8				33.2				0.07	0.4	
E PARK AVE	135.1					562.9		210.4				0.50	3.2	
SPRING ST	70.3					293.1		151.0				0.26	1.7	
ALLEY 189+00		19.4				38.8		30.5				0.05	0.3	
ALLEY 190+65		18.7				37.3						0.05	0.3	
AUTUMN AVE		52.7		59.2				105.3				0.15	0.9	
BROWN AVE		29.7		33.4				54.7				0.08	0.5	
ALLEY 193+03		15.6				31.2						0.04	0.3	
ALLEY 194+20		12.3				24.6						0.03	0.2	
WADSWORTH ST		18.8		21.1				39.1				0.05	0.3	
ALLEY 196+76		6.3		12.6								0.02	0.1	
DELEVAN		20.2		22.7				41.0				0.06	0.4	
REBECCA AVE		27.7		31.2				66.5				0.08	0.5	
TILLOTSON AVE		39.9		44.9				85.8				0.11	0.7	
ALLEY 201+69		16.8				33.6						0.05	0.3	
MARY AVE		32.0		36.0				49.4				0.09	0.6	
ALLEY 205+61		11.7				23.5						0.03	0.2	
HIGH SCHOOL AVE		46.3		52.0				73.9				0.13	0.8	
HIGH SCHOOL ST		25.8		29.1				41.1				0.07	0.5	
UNION AVE		45.2		50.8				102.5				0.13	0.8	
WILSON AVE		27.8		31.3				53.3				0.08	0.5	
INDIANA AVE	43.5					181.1		111.6				0.16	1.0	
ALLEY 223+94		16.0				31.9						0.04	0.3	
ILLINOIS AVE	39.6					164.9		89.3				0.15	0.9	
MEADOW LN		37.5		42.2				58.7				0.10	0.7	
CALIFORNIA AVE	26.8					111.5		59.8				0.10	0.6	
CLAREMONT CT		22.9		25.8				34.9				0.06	0.4	
MOUNDS AVE		19.9		22.4				42.5				0.06	0.4	
CUMBERLAND AVE		22.9		25.7				34.9				0.06	0.4	
KEEBLER CUL DE SAC	75.9					316.1		109.4				0.28	1.8	
E WICKLIFFE AVE OVERLAY	54.2										644.9	0.20	1.3	
E PARK AVE OVERLAY	66.2										787.7	0.25	1.6	
TOTAL		7518.1				26312.3		2171.7	39157.9	84.2	5773.4	2912.0	18.55	118.6

TEMPORARY RAMP SCHEDULE	
LOCATION	TEMPORARY RAMP (SQ YD)
IL RTE 159	
163+05.00	42.8
167+65.00	40.7
227+25.00	54.6
237+50.00	54.6
ALLEY @ 168+75	
1+00.00	11.9
E MADISON AVE	
2+07.00	23.1
WICKLIFFE AVE	
57+20.00	18.9
58+00.00	20.0
62+00.00	20.0
61+67, 38' LT	8.3
61+78, 38' RT	6.1
63+00.00	15.0
VALLEY AVE	
1+20.00	17.9
VALLEY LN	
1+65.00	8.2
E PARK AVE	
66+00.00	11.7
SPRING ST	
82+25.00	14.4
ALLEY @ 190+65	
1+26.00	8.2
AUTUMN AVE	
91+65.00	20.1
BROWN AVE	
0+90.00	20.1
ALLEY @ 193+03	
0+96.00	10.4
ALLEY @ 194+20	
0+86.00	9.7
WADSWORTH	
0+70.00	23.1
ALLEY @ 196+76	
0+67.00	8.2
DELEVAN ST	
198+26, 70' RT (159 ALIGNMENT)	18.6
SUBTOTAL (1)	486.6

TEMPORARY RAMP SCHEDULE (CONT'D)	
LOCATION	TEMPORARY RAMP (SQ YD)
REBECCA AVE	
1+10.00	20.8
ALLEY @ 199+96	
0+57.00	10.4
TILLOTSON	
4+32.50	17.9
MARY	
0+90.00	23.1
ALLEY @ 201+69	
1+17.00	10.4
ALLEY @ 205+61	
1+05.00	8.2
HIGH SCHOOL AVE	
1+15.00	27.5
207+38, 67' RT (159 ALIGNMENT)	28.3
UNION AVE	
1+60.00	16.4
WILSON	
100+88.00	19.4
INDIANA AVE	
1+80.00	14.4
ALLEY @ 223+94	
1+00.00	11.9
ILLINOIS AVE	
1+45.00	15.6
MEADOW LN	
1+00.92	20.8
CALIFORNIA AVE	
1+10.00	13.3
CLAREMONT CT	
0+67.53	21.6
MOUNDS AVE	
234+22.02, 69' LT (159 ALIGNMENT)	16.4
CUMBERLAND ST	
236+53, 68' RT (159 ALIGNMENT)	25.3
IL RTE 159	
163+05 TO 237+50	496.3
SUBTOTAL (2)	5284.7
SUBTOTAL (1)	486.6
SUBTOTAL (2)	5284.7
TOTAL	5771